

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-00590-00-01
Spot: SWNWNW Sec/Twnshp/Rge: 35-5S-27W
4320 feet from S Section Line, 5039 feet from E Section Line
Lease Name: N W ADELL Well #: 7W
County: DECATUR Total Vertical Depth: 3907 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3907	0	200 SX
SURF	8.625	279	0	200 SX

126.98

Well Type: EOR *33045* UIC Docket No: E15099.2 Date/Time to Plug: 12/18/2008 11:00 AM
Plug Co. License No.: ~~4072~~ Plug Co. Name: PLAINS, INC *H 2 Plains LLC* *KCC/PTA Licensing*
Proposal Rcvd. from: PAT CANADAY Company: VESS OIL CORPORATION Phone: (316) 682-1537

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 18 sxs gel - 900# hulls.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/18/2008 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 279' w/200 sxs cement.
5 1/2" production casing set at 3907' w/200 sxs cement.
PBSD 3803'. TD 3907'.
5 1/2" production casing perforated at 2800' - pumped 200 sxs.
Perforated at 1450' - pumped 225 sxs.
Perforated at 900' - pumped 200 sxs.
Top down 8 5/8" surface casing with 100 sxs.
Production casing had holes at 1460'.
12/18/2008 - Ran tubing to 3400' - tagged solid bridge.
Pulled tubing to 3370' - pumped 80 sxs cement with 600# hulls.
Pulled tubing to 2500' - pumped 18 50# sxs gel.
Pulled tubing to 2240' - pumped 25 sxs cement
Pulled tubing to 1465' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 330' - pumped 50 sxs cement - cement to surface.
Pulled tubing to surface.
Connected to 5 1/2" production casing - pumped 10 sxs cement.
Max. P.S.I. 400#. S.I.P. 0#.
Connected to 8 5/8" surface casing - pumped 20 sxs cement.
Max. P.S.I. 250#. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3649	3773		LKC

INVOICED
DATE 1-23-09
INV. NO. 2009061089

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 07 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: SOS CEMENTING SERVICE-TICKET #306.

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

PKT

R. W. SHIELDS

#1

TAYLOR

35-5-27W

SW NW NW

Contr.

DECATUR

County

E-2659RB

Comm. 4-16-52

Comp. 6-13-52

IP 265 BOPD (LANS)

PHY POT

Tops	Depth	Datum
ANH	2240	419
HEEB	3608	-949
TOR	3629	-970
LANS	3644	-985
B/KC	3858	-1199
ID	3906	-1247

Casing

8" 279
 5" 3905

PERF 12 S, 3821-25:
 11 S, 3829-33: 24 S
 3338-46: SWB 3 1/2 BOPH/
 7 HRS: ACID 500: SWB
 1.0 BOPH/4 HRS

ADELL NORTHWEST POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS