

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-21582-00-00
Spot: NWNESESE Sec/Twnshp/Rge: 10-21S-24W
1100 feet from S Section Line, 580 feet from E Section Line
Lease Name: FRUSHER 'B' Well #: 1
County: HODGEMAN Total Vertical Depth: 4473 feet

Operator License No.: 9067
Op Name: DAMAR RESOURCES, INC.
Address: 234 W 11TH STE A PO BOX 70
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	306		WITH 190 SX CMT

145.37

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/31/2008 7:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: TONY MARTIN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 80 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 12/31/2008 9:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:
1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 720' WITH 80 SX CMT. 3RD PLUG AT 330' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:
INVOICED
DATE 1-27-09
INV. NO. 2009061104

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 09 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.
Plugged through: DP

District: 01
RECEIVED
JAN - 7 2009
KCC

Signed Eric MacLaren
(TECHNICIAN)
Form CP-2/3