

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27393-00-00
Spot: SENESW Sec/Twnshp/Rge: 13-25S-13E
1760 feet from S Section Line, 2310 feet from W Section Line
Lease Name: LIEBAU Well #: L-3
County: WOODSON Total Vertical Depth: 1462 feet

Operator License No.: 34106
Op Name: HARRIS, DAVID
Address: 636 HWY 105
TORONTO, KS 66777

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	40	0	

47.52

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/19/2008 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: DAVID HARRIS Company: DAVID HARRIS Phone: (620) 637-2674

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 1462'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 700' AND TO PLACE A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 09/19/2008 12:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

2" TUBING WAS RAN INTO THE WELL 0 TO 1462'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE TUBING TO 1462'. THE TUBING WAS PULLED TO 700' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

INVOICED
DATE 1-27-09
INV. NO. 2009061109

RECEIVED
KCC DISTRICT #3
DEC 31 2008
CHANUTE, KS

CPT

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 12 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

[Handwritten initials]