

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23277-00-00  
Spot: NWNWNW Sec/Twnshp/Rge: 31-11S-15W  
70 feet from N Section Line, 330 feet from W Section Line  
Lease Name: JULIA B UNIT Well #: 31-1  
County: RUSSELL Total Vertical Depth: 3550 feet

Operator License No.: 33335  
Op Name: IA OPERATING, INC.  
Address: 9915 W 21ST ST, STE B  
WICHITA, KS 67205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3547	1620	w/175 sxs cmt
SURF	8.625	943	0	w/500 sxs cmt <u>115.38</u>
T1	2.375	3261		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/08/2009 11:00 AM  
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS  
Proposal Rcvd. from: MIKE STANTON Company: IA OPERATING, INC. Phone: (316) 721-0036

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 4% gel - 400# hulls.  
Alt I - 8 5/8" at 943'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/08/2009 3:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 75 sxs 60/40 pozmix - 4% gel with 200# hulls - displaced to 2500'.  
Superior Wireline shot casing off at 1620' - pulled one joint - 1580'.  
Allied pumped 190 sxs cement with 200# hulls - pulled 5 1/2" casing to 980'.  
Allied pumped 25 sxs cement with 100# hulls - pulled to 200'.  
Allied pumped 30 sxs - cwc - pulled casing out.  
Topped off with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3222	3226		
3173	3175		
3168	3171		
3036	3038		
2980	2982		
2744	2747		

**INVOICED**

DATE 1-27-09  
INV. NO. 2009061112

RECEIVED  
KANSAS CORPORATION COMMISSION

JAN 15 2009

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

JAN 12 2009

PK

IA OPERATING  
WICHITA KS 67212

31-11S-15W  
95°N, C N/2 NW NW NW

#31-1 JULIA B UNIT

site 3-1/2 S & 6 W OF PARADISE KS      dy: RUSSELL      API 15-167-23277  
contr: MURFIN DRILLING #16      field BLUE HILL NE EXT (1/4 NE)  
geol: RANDALL KILIAN  
fr date 01/18/2005      spd date 02/28/2005      drlg comp 03/07/2005      card issued 06/06/2005      test revised 06/06/2005

•		

ELV: 1777 KB, 1772 GL  
tops.....depth/datum  
PBTB .....3535 -1758  
RTD.....3550 -1773  
NO TOPS RPTD

IP status:  
OIL, LKC , INTV NA , 03/07/2005  
CSG: 8-5/8" 943 (ALT 1), PROD CSG NA  
NO CORES  
DSTS TAKEN - DETAILS NA  
TRGT ZN: LKC (OIL), PTD 3600 (ARB), MICT - CO, PB 3535,  
PF (LKC) INTV NA, SWB DWN, SO, POP, OIL WELL  
(POTENTIAL NOT RPTD), 3/7/2005 - TIGHT HOLE - NO  
OTHER INFO AVAILABLE - TEMP COMP 6/6/2005

COPYRIGHT 2005  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS