

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20142-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 30-28S-31W
1250 feet from N Section Line, 1350 feet from W Section Line
Lease Name: KOELLING Well #: 1
County: HASKELL Total Vertical Depth: 2798 feet

Operator License No.: 6568
Op Name: KAISER-FRANCIS OIL COMPANY
Address: PO BOX 21468
TULSA, OK 74121

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2791	738	WITH 200 SX CMT
SURF	8.625	563		WITH 400 SX CMT 90.94

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/05/2009 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL
Date/Time Plugging Completed: 01/05/2009 6:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

TUBING PARTED @ 2570'. TOP OF FISH IN TUBING @ 1362'. 1ST PLUG PUMP 20 SX CMT & 100# HULLS DOWN 2 3/8" TUBING. PTOH. 2ND PLUG SHOT 4 1/2" CASING @ 738'. LAID DOWN 1 JOINT. LOADED HOLE WITH MUD, MIXED & PUMPED 65 SX CMT. 3RD PLUG PULLED CASING TO 40' & PUMPED 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
2732	2774		
INVOICED DATE <u>1-27-09</u> INV. NO. <u>200906114</u>			
RECEIVED KANSAS CORPORATION COMMISSION JAN 09 2009 CONSERVATION DIVISION WICHITA, KS			

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01



Signed

(TECHNICIAN)