

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22130-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 16-18S-27W
975 feet from S Section Line, 1915 feet from W Section Line
Lease Name: BSQ STANLEY Well #: 13-16
County: LANE Total Vertical Depth: 4700 feet

Operator License No.: 34056
Op Name: MAK-J ENERGY KANSAS LLC
Address: 1600 N BROADWAY, STE 1740
DENVER, CO 80202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| SURF | 8.625 | 266 | | WITH 175 SX CMT |

152.75

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 11/12/2008 7:00 AM

Plug Co. License No.: 31120 Plug Co. Name: PELICAN HILL OIL & GAS, INC.

Proposal Rcvd. from: ROGER MOSES Company: _____ Phone: (785) 656-1729

Proposed Plugging Method: TOTAL 265 SKS, 2140'-50 SKS, 1300'-80 SKS, 600'-40 SKS, 300'-50 SKS, 60'-20 SKS, RAT HOLE-15 SKS, MOUSE HOLE 10 SKS. P & A @ 09:00 11/12/2008 & AUTHORIZED BY MICHAEL MAIER, KCC @ 11/11/08 @ 17:34

Plugging Proposal Received By: MICHAEL MAIER
Date/Time Plugging Completed: 11/12/2008 9:00 AM

WitnessType: NONE
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

1ST PLUG AT 2140' WITH 50 SX CMT. 2ND PLUG AT 1300' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 40 SX CMT. 4TH PLUG AT 300' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

INVOICED
DATE 1-27-09
INV. NO. 2009061114

RECEIVED
KANSAS CORPORATION COMMISSION


JAN 09 2009

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Michael Maier
(TECHNICIAN)

Form CP-2/3