

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Shakespeare Oil Company, Inc.  
Address: 202 West Main Street, Salem, IL 62881  
Phone: (618) 548-1585 Operator License #: 7311  
Type of Well: D&A Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 12/23/08 (Date)  
by: Jerry Stapleton (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
N/A Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-069-20311-00-00  
Lease Name: Elwell  
Well Number: 1-11  
Spot Location (QQQQ): SE - NE - SE - NW  
1754 Feet from  North /  South Section Line  
2314 Feet from  East /  West Section Line  
Sec. 11 Twp. 28S S. R. 29  East  West  
County: Gray  
Date Well Completed: 12/23/08  
Plugging Commenced: 12/24/08  
Plugging Completed: 12/24/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	225'	8 5/8"	415'	0'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rotary mud from 5300' to 1860', 1610' to 840', and 200' to 60'.

Cement plugs from 1860' to 1610', 840' to 450', 450' to 200', 60' to 0', 30 sx rathole, 20 sx mousehole

Total 250 sx 60/40 Pozmix - 4% gel & 1/4#/sx flo-seal

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Sterling Drilling Company License #: 5142  
Address: P. O. Box 1006, Pratt, KS 67124  
Name of Party Responsible for Plugging Fees: Shakespeare Oil Company, Inc.  
State of Illinois County, Marion, ss.

JAN 20 2009

CONSERVATION DIVISION  
WICHITA, KS

Donald R. Williams, Vice President (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Donald R Williams

(Address) 202 West Main Street, Salem, IL 62881



Subscribed and SWORN TO before me this 14th day of January, 2009  
Melissa A. Noel My Commission Expires: 11-16-11  
Notary Public