

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC
Address: 410 17th Street Ste. 900
Phone: (303) 893-5090 Operator License #: 33476
Type of Well: D&A Gas KCCPT per CP213 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 01/05/2009 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Krider Depth to Top: _____ Bottom: _____ T.D. 2772'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 171-20048 - 00-00
Lease Name: Dearden
Well Number: 1-20
Spot Location (QQQQ): S2 - SW - NE - NE
1200 Feet from North / South Section Line
1000 Feet from East / West Section Line
Sec. 20 Twp. 19 S. R. 31 East West
County: Scott
Date Well Completed: 10/1972
Plugging Commenced: 01/05/2009
Plugging Completed: 01/05/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Krider	Gas	367	surf	8-5/8"		
		2750	surf	5-1/2"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RU Allied Cement Co. Hook up to csg. Injection rate down casing-3 bpm @ 500#. Plug down casing as follows: Mix 80 sxs 60/40 Poz 4% gel, 100# hulls 105 sxs 60/40 Poz 4% gel. Displace down casing & psi to 700#. Shut in with 500# standing. Hook up to annulus. Mix & displace 165 sxs 60/40 Poz 4% gel down annulus. Shut in 0# press, cement standing @ surface. Job complete at 11:45 am. KCC representative on location, Ken Jehlik.

Name of Plugging Contractor: Allied Cementing Company License #: 145725 99996
Address: P.O. Box 31 Russell, KS

KCCPT per CP213

RECEIVED
KANSAS CORPORATION COMMISSION


Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC JAN 16 2009

State of Colorado County, Denver, ss.
Cassandra Parks (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Cassandra Parks
(Address) 410 17th St. Suite 900 Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 14th day of January 20 09
Elizabeth B Kauer My Commission Expires: 7/1/2010
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PK

