

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Herman Loeb

Address: PO Box 524, Lawrenceville, ILL 62439-0524

Phone: (618) 943-2227 Operator License #: 3273

Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 1/6/09 (Date)

by: Case Morris (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Morrow Depth to Top: 5132 Bottom: 5140 T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

02

API Number: 15 - 199-20, 162-00-00

Lease Name: Krautkrampfer KCC Pkt Den

Well Number: 3-30 CP2/3

Spot Location (QQQQ): C - N2 - NE - 4

4620 Feet from  North /  South Section Line

1320 Feet from  East /  West Section Line

Sec. 30 Twp. 15 S. R. 42  East  West

County: Wallace

Date Well Completed: 10/18/88 *original*

Plugging Commenced: 1/5/09

Plugging Completed: 1/6/09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Morrow		Surface	430	8 5/8		
		Surface	5279	5 1/2		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Tubing sanded in 5 1/2 casing @ 4070 ft. Casing holes squeezed from 2472-3945 ft. w/ 850 sx. Ran tubing to 4040 ft. Connected to tubing, pumped 150 sx cement & 400# hulls. Fluid to surface. Pulled tubing to 2400 ft. pumped 150 sx cement & 400# hulls. Good returns. Pulled tubing to 775 ft. Pumped 60 sx cement & 100# hulls. Cement to surface. Pulled tubing to surface. Connected to 5 1/2 production casing, pumped 20 sx. Maximum pressure 400#, SIP 0#. Connect to 8 5/8 S.P. pump 15 sx cement. Maximum pressure 450#, SIP 300#

Name of Plugging Contractor: Eastern Colorado Well Service LLC License #: 32997

Address: PO Box 244, Cheyenne Wells, CO 80810

Name of Party Responsible for Plugging Fees: Herman Loeb

State of \_\_\_\_\_ County, \_\_\_\_\_, ss.

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 16 2009  
CONSERVATION DIVISION  
WICHITA, KS

Shane Peiton (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_


(Address) PO Box 782 Cheyenne Wells CO 80810

SUBSCRIBED and SWORN TO before me this 13<sup>th</sup> day of January, 2009

David Jones My Commission Expires: May 1, 2012

Notary Public 150 S. 1st Street E  
Cheyenne Wells, Colo. 80810

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



PKT