

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: FIML Natural Resources, LLC
Address: 410 17th Street Ste. 900
Phone: (303) 893-5090 Operator License #: 33476
Type of Well: D&A Docket #:
The plugging proposal was approved on: 11/24/2008
by: Rick Williams
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-109-20820-00-00
Lease Name: Pope
Well Number: 11C-19-1135
Spot Location (QQQQ): SW - SW - NE - SW
1425 Feet from North / South Section Line
1500 Feet from East / West Section Line
Sec. 19 Twp. 11 S. R. 35 East West
County: Logan
Date Well Completed: NA
Plugging Commenced: 11/30/2008
Plugging Completed: 11/30/2008

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Row 1: 392' surface 8-7/8" 11/22/2008

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set plug #1 f/ 2700-2596' w/ 25 sx (6.2 bbl) 60/40 Pozmix w/ 4% gel & 0.25 pps floeal. Set plug #2 f/ 1682-1266' w/ 100 sx (25.1 bbl) 60/40 Pozmix.
Set plug #3 f/ 442-342' w/ 40 sx (10.0 bbl) 60/40 Pozmix. Set plug #4 f/ 40'-surface w/ rubber plug & 10 sx (2.5 bbl) 60/40 Poz
Plugged rat hole/mouse hole w/ 30 sx (7.5 bbl)/15 sx (3.7 bbl) 60/40 Pozmix. All Pozmix had 4% gel and 0.25 pps floeal.

Fluid between all plugs was 9.2 ppg, 52 sec/qt viscosity & 5600 ppm CL mud.

Name of Plugging Contractor: Allied Cementing Company Murfin Drilling Co Inc License #: 115725
Address: P.O. Box 31 Russell, KS
RECEIVED KANSAS CORPORATION COMMISSION
KCCPRT Per CP 2/3 JAN 16 2009

Name of Party Responsible for Plugging Fees: FIML Natural Resources, LLC
State of Colorado County, Denver, ss.

Cassandra Parks (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 410 17th Street Suite 900 Denver, CO 80202

SUBSCRIBED and SWORN TO before me this 10th day of December, 2008
Elizabeth B. Kauer My Commission Expires: 12-1-2010
Notary Public