

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Thomason Petroleum Inc.
Address: Box 875, Hays, Ks. 67601
Phone: (785) 625-9045 Operator License #: 9957
Type of Well: D&A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 12/11/2008 (Date)
by: David Wann (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-163-23,786-00-00
Lease Name: Keller
Well Number: 1
Spot Location (QQQQ): n2 - SW - SW - NE *KCC PKT Per RBDMs*
2050 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 35 Twp. 10 S. R. 20 East West
County: Rooks
Date Well Completed: 12/18/2008
Plugging Commenced: 8:30 PM 12/17/08
Plugging Completed: 12:45 AM 12/18/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		Surface	224	8 5/8"	224	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @ 3750' w/25 sks, 2nd Plug @ 1640' w/25 sks, 3rd Plug @ 925' w/100 sks, 4th Plug @ 275' w/40 sks, 5th Plug @ 40' w/10 sks,
30 sks in Rat Hole, 15 sks in Mouse Hole, Circulated 1st plug 15 Min w 56 vis Mud. Plugs displaced with mud. Total 245 sks
60/40 Pos 4%gel/ 1/4#CF/sk. Buy Quality Oilwell Cementing- Completed @ 12:45 AM 12/18/2008

RECEIVED
KANSAS CORPORATION C.


Name of Plugging Contractor: Discovery Drilling co. Inc. License #: 31548
Address: P.O. Box 763 Hays, Kansas 67601

JAN 15 2009

Name of Party Responsible for Plugging Fees: Thomason Petroleum Inc.
State of Kansas County, Ellis, ss.

CONSERVATION DIV.
WICHITA, Kc

Steven Thomason President of Thomason Petroleum Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) Box 875, Hays, Ks. 67601

SUBSCRIBED and SWORN TO before me this 10th day of January, 20 09
Brian Karlin My Commission Expires: 8-27-09
Notary Public

PKT