

Notice: Fill out COMPLETELY
and return to Conservation Division
at the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: C & M Oil Company

Address: 1940 Road 10

Phone: (620) 330-3387

Operator License #: 31246

Type of Well: injection

Docket #: E-24,661

(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other)

(If SWD or ENHR)

The plugging proposal was approved on: 9/22/08

(Date)

by: Larry Marchant

(KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No

If not, is well log attached? ☐ Yes ☐ No

Producing Formation(s): List All (If needed attach another sheet)

Layton

Depth to Top: 670 Bottom: 690 T.D. 700

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 019-21,702 - 00-01

Lease Name: Briggs

Well Number: 6

Spot Location (QQQQ): SE - NW - NE - NE

4875

Feet from ☐ North / ☒ South Section Line

0720

Feet from ☒ East / ☐ West Section Line

Sec. 8 Twp. 32 S. R. 12 ☒ East ☐ West

County: Chautauqua

Date Well Completed: 1979 *original*

Plugging Commenced: 9/25/08

Plugging Completed: 9/25/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Layton	oil					
		surface	40	7"	40'	0
		surface	701'	4 1/2"	671'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran 1" pipe to 700', gel hole with 5bbl gel water, spotted 10 sks cement at 700'.

Pulled 1" pipe up to 350' cemented to surface with 35 sks cement.

Pulled 1" pipe out and topped off well with cement.

Name of Plugging Contractor: Elmore's Inc.

License #: 32884

Address: P. O. Box 87 Sedan, Kansas 67361

Name of Party Responsible for Plugging Fees: C & M Oil Company

State of Kansas

County, Chautauqua

ss.

Clay Beckenholdt

(Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature)

(Address) 1940 Road 10 Moline, Kansas 67353


SUBSCRIBED and SWORN TO before me this 12th day of January

20 09

Notary Public

My Commission Expires: 5/6/10

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



STATEMENT

8004

ELMORE'S INC.

Box 87 - 776 HWY99

Sedan, KS 67361

Cell: (620) 249-2519

Eve: (620) 725-5538

Date

9-25-08

Customer

Address

City

State

Zip

Qty.	Description	Price	Amount
45	SKS Cement	7.95	357.75
1	Sk Gel	15.00	15.00
700'	1" Tubin	.10	70.00
2 hr	Cement Pump	100.00	200.00
2 hr	Water Truck	80.00	160.00
1	Bulk Tank	80.00	80.00
			882.75
	Plug Tab Brigs #6	Tax	55.61
	E-24,661		938.36
	Ran 1" To 700' Gel Hole		
	With 5BBL Gel Water Spotted 10 SKS		
	Cement At 700' Pulled 1" Up to 350'		
	Cemented To Surface With 35 SKS		
	Cement Pulled 1" Out Topped Off		
	Well CK# 1603		
	\$1000.00		
	Credit		(\$61.64)

Thank You -- We appreciate your business!

Rec'd. by

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 13 2009

CONSERVATION DIVISION
WICHITA, KS