

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

Please TYPE Form and File ONE Copy

API # 15 - Drilled-1951 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 8-17-51

Well Operator: John J. Darrah Originally Westgate-Greenland KCC License #: 5088  
(Owner / Company Name) (Operator's)

Address: 225 N. Market #300 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: ( 620 ) 786 - 4046

Lease: Rathbun "A" Well #: 4 Sec. 16 Twp. 17 S. R. 8  East  West

   - NW - SW - NE Spot Location / QQQQ County: ELLSWORTH

330 3630 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line) *KCC PRT*

1650 2310 Feet (in exact footage) From  East - /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: none Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks

Surface Casing Size: 8 5/8 Set at: 204 Cemented with: 140 Sacks

Production Casing Size: 5 1/2 Set at: 3268 Cemented with: 75 Sacks

List (ALL) Perforations and Bridgeplug Sets: 3188-3228

Elevation: 1716 ( G.L. /  K.B.) T.D.: 3266 PBTD: \_\_\_\_\_ Anhydrite Depth: 794  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): \_\_\_\_\_

As directed **RECEIVED**  
KANSAS CORPORATION COMMISSION

**DEC 22 2008**

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No CONSERVATION DIVISION  
WICHITA, KS

If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: George Stoeppelwerth

Phone: ( 620 ) 786 - 4046

Address: above City / State: \_\_\_\_\_

Plugging Contractor: Mike's Testing & Salvage KCC License #: 31529  
(Company Name) (Contractor's)

Address: PO Box 457, Chase, KS 67524-0457 Phone: ( 620 ) 938 - 2945

Proposed Date and Hour of Plugging (if known?): as equipment is available

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 12/19-08 Authorized Operator / Agent: *George Stoeppelwerth* (Signature)

*dist 2*  
*PT*

DRILLER'S LOG

COMPANY: Westgate-Greenland Oil Co  
 CONTRACTOR: Jackson Drilling Corporation  
 FARM: Rathbun "A" - 4  
 LOCATION: NW SW NE Sec. 16-17-8W  
 Ellsworth County, Kansas  
 COMMENCED: September 22, 1951  
 COMPLETED: October 3, 1951 - Rotary  
 October 11, 1951 - Cardwell  
 ELEVATION: 1716 DF

0	to	20	Clay and hard sand
20	to	275	Shale and shells
275	to	310	Red bed
310	to	325	Lime
325	to	870	Shale and shells
870	to	1030	Shale, salt and shells
1030	to	1190	Lime and shale
1190	to	1635	Lime
1635	to	2420	Lime and shale
2420	to	2680	Lime
2680	to	2776	Lime and shale
2776	to	3145	Lime
3145	to	3174	Conglomerate
3174	to	3195	Sand
3195	to	3203	Lime and shale
3203	to	3268	Lime
		3268	T. D. (RB)

3176  
 1718  
 ---  
 1458

3228  
 1718  
 ---  
 1510

Set 20 1/2 feet 5/8" 36# surface. Cemented with 140 sacks cement with 2 sacks cal. chloride.

Set 5 1/2" casing at 3268 (RB). Cemented with 75 sacks Cement.

Drill Stem Tests: 3182-3241. Packer failed.  
 3188-3241. Tool plugged.

TOPS: Heebner 2652. Brown Lime 2773. Lansing 2794.  
 Base KC 3112. ~~Shinn~~ Simpson Shale 3157.  
 Arbuckle 3176.

Perf. 140 shots 3188-3228, Swab 1/2 BO natural- 1000 GA  
 Swabbed 10 BO in 6 hours.

10/11/51 Filed 25 BOPD Temporary Productivity affidavit.

C E R T I F I C A T E

I, Harold A. Burt, do hereby certify that the above and foregoing is a true and correct copy of log of the Rathbun "A"-4. Section 16-17-8W, Ellsworth County, Kansas, as reflected by files of the Westgate-Greenland Oil Company.

*Harold A. Burt*  
 Harold A. Burt

Subscribed and sworn to before me, a Notary Public, within and for Sedgwick County, Kansas, this 25th day of October, 1951.

My Commission expires May 25, 1953.

*Esther Russell*  
 Notary Public



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

DARRAH, JOHN JAY, JR.  
225 N MARKET STE 300  
WICHITA, KS 67202-2024

January 02, 2009

Re: RATHBUN A #4  
API 15-053-00794-00-00  
16-17S-8W, 3630 FSL 2310 FEL  
ELLSWORTH COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after July 1, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000