

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15-055-21918-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date spud 07/08/2006

Well Operator: C. H. Todd, Inc. KCC License #: 5055
(Owner / Company Name) (Operator's)

Address: 100 S. Main, Suite 415 City: Wichita

State: KS Zip Code: 67202 Contact Phone: (316) 264-7566

Lease: Winters Well #: 1-8 Sec. 8 Twp. 22 S. R. 31 East West

C SE Spot Location / QQQQ County: Finney

1320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1320 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: TA'd non comm gas well

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8", 23# Set at: 425' Cemented with: 275 Sacks

Production Casing Size: 4 1/2", 10.5# Set at: 2780' Cemented with: 450 Sacks

List (ALL) Perforations and Bridgeplug Sets: 2712'-2728'

Elevation: 2912 (G.L. / K.B.) T.D.: 2790 PBDT: 2763 Anhydrite Depth: _____
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Pump down csg w/ 400# hulls w/ 125 sx cmt, max PSI 300#, SI @ 300#. Hook up to 8 5/8" annulus, pump 100 sx cmt, max PSI 200#, SI @ 200#. Cut off casing, weld cap.

**RECEIVED
KANSAS CORPORATION COMMISSION**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

DEC 22 2008

If not explain why? Filed w/ ACO-1

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: David B. Pauly

Phone: (316) 264-7566

Address: 100 S. Main, Suite 415 City / State: Wichita, KS 67202

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: 99996
(Company Name) (Contractor's)

Address: PO Box 31, Russell, KS 67665 Phone: (785) 483-2626

Proposed Date and Hour of Plugging (if known?): _____

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/12/08 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

12/17/08

RESUBMIT

AA

Handwritten Signature

Dist 1
PKT



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

C. H. TODD, INC.
1000 N TYLER STE 100
WICHITA, KS 67212-3276

January 02, 2009

Re: WINTERS #1-8
API 15-055-21918-00-00
8-22S-31W, 1320 FSL 1320 FEL
FINNEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after July 1, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888

Sincerely,

Steve Bond
Production Department Supervisor