

WELL PLUGGING RECORD 15-065-20327-00-01

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 27 TWP. 9 RGE. 23 E/W
 Location as in quarters or footage from lines:
 SE/SE/NW

Lease Owner Frontier Oil Company
 Lease Name Riffel "C" Well No. #1
 Office Address 1437 N. Franklin - Russell, Ks. 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced September 1, 1982
 Plugging completed September 7, 1982
 Reason for abandonment of well or producing formation Depleted

Locate Well
 correctly on above
 Section Platt.

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom _____ T.D. 3920'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	203'	NONE
				4 1/2"	3919'	1497.66'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 3800' and four (4) sacks cement.
 Shot pipe @ 3000, 2500', 2000', 1800', 1600' and 1500'.
 Pulled thirty-seven (37) joints 4 1/2" casing.
 Squeezed well with four (4) sacks hulls, thirty (30) sacks
 gel, seventy (70) sacks cement, ten (10) sacks gel, sixty (60)
 sacks cement ----- released plug ----- and pumped ten (10)
 sacks 50/50 pozmix cement with 6% added gel and 3% calcium
 chloride. Final pressure 200 psi.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.


STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend,
 (Address) Ks. 67530

SUBSCRIBED AND SWORN TO before me this 21st day of September 1982

My Commission expires



Margaret Prosser
 Notary Public.
 STATE CORPORATION COMMISSION
 9-22-82
 SEP 22 1982