

15-065-20325-00-01

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER compl 4/71

LEASE NAME Law A

WELL NUMBER 2

SPOT LOCATION NW NW SE

SEC. 27 TWP. 9S RGE. 23W (E) or (W)

COUNTY Graham

Date Well Completed 4/71

Plugging Commenced 12/17/86

Plugging Completed 12/17/86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Murfin Drilling Company

ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202

PHONE # ( ) 267-3241 OPERATORS LICENSE NO. 6033

Character of Well oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6-Hays

Is ACO-1 filled? no If not, is well log attached? no

Producing formation LKC Depth to top 3692' bottom 3856' T.D. 3969'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	208'	-
				4 1/2"	3974'	-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Connected to 8 5/8" & 4 1/2" annulus. Pumped 50 sx. Econolite cement w/1 sx hulls. Max 600 psig, SIP 200 psig. Connected to 4 1/2" csg. Pumped 150 sx. Econolite cement w/5 sx. hulls. Max 600 psig, SIP 400 psig. Filled to surface w/.50 yds of Redi-mix. Volume of cement pumped down annulus is = to 774'. Volume of cement pumped down 4 1/2" csg. is = to 6050'.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Murfin Drilling Company License No. 6033  
Address Wichita, KS

1-30-87

STATE OF Kansas COUNTY OF Sedgwick, ss.

Larry M. Jack, Eastern Div., Prod. Mgr. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That JAN 30 1987 I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

STATE CORPORATION COMMISSION

CONSERVATION DIVISION  
Wichita, Kansas

(Signature) By: Larry M. Jack  
(Address) Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 29 day of Jan., 1987

Kerran Redington Notary Public

My Commission expires: 2/6/90

