

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Bldg.
 Wichita, Kansas 67202

Form CP-4
 Rev. 12-15-80

15-065-20294-00-00

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Graham SEC. 27 TWP. 9S RGE. 23 E/W
 Location as in quarters or footage from lines:
NE/NE/SW

	X		

Locate Well
 correctly on above
 Section Platt.

Lease Owner The National Oil Company (Ohio)
 Lease Name Benoit Well No. 1
 Office Address 37 West Broad Street, Columbus, Ohio 43215
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 1-70
 Application for plugging filed 11-18-88
 Plugging commenced 12-10-88
 Plugging completed 12-11-88
 Reason for abandonment of well or producing formation Non-commercial quantities of oil producing

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow

Producing formation Lansing/Kansas City Depth to top 3616 bottom 3896 T.D. 3920

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Lansing - Kansas	Oil & Water	3736	3896	4 1/2"		None
Topeka	Water	3612	3616	4 1/2"		None

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set.

300 sacks; 65/35 Thrifty lite w/10% Gel, 500 lbs. cotton seed hulls.
15 sacks of cement was pumped between the 8-5/8" surface casing and 4 1/2" production casing.
Pressured to 500 psi held for 10 minutes. Shut in.
Pumped 285 sacks cement down 4 1/2" production casing - 200 psi max - finished @ 200 psi. Shut in.
Dug out well head and casing - 4 feet below ground level - cut of casing strings 12-13-88

RECEIVED
 STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Eagle Well Service - B.J. Titan Services
Garr R. Roberts, Consulting Service

FEB 27 1989

2-27-89

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF Ohio COUNTY OF Franklin, ss.
 I, James W. Kincaid, Executive Vice President (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

FEB 15 1989

Wichita, Kansas

(Signature) James Kincaid Exec. VP
 37 W. Broad St. #1100, Columbus, OH 43215
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of February, 1989



Susan P. Rouse
 Notary Public.

My Commission expires: 1-31-94

SUSAN P. ROUSE
 NOTARY PUBLIC, STATE OF OHIO
 MY COMMISSION EXPIRES JAN. 31, 1994