

15 065-00006-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
11 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Trego GRAHAM County. Sec. 27 Twp. 9 Rge.      (E) 23 (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NE

Lease Owner Chief Drilling Co., Inc.

Lease Name SPARKS Well No. 1

Office Address Box 797 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6/5 19 62

Application for plugging filed 6/5 19 62

Application for plugging approved 6/5 19 62

Plugging commenced 6/5 19 62

Plugging completed 6/5 19 62

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production      19    

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty - Hays, Kansas

Producing formation      Depth to top      Bottom      Total Depth of Well 3960 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION     | CONTENT | FROM | TO   | SIZE | PUT IN | PULLED OUT |
|---------------|---------|------|------|------|--------|------------|
| Sand & Gravel |         | 0    | 200' |      | 200'   | None       |
|               |         |      |      |      |        |            |
|               |         |      |      |      |        |            |
|               |         |      |      |      |        |            |
|               |         |      |      |      |        |            |
|               |         |      |      |      |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Set wooden plug at 550' with 20 sacks cement thru drill pipe  
Set wooden plug at 180' with 20 sacks cement thru drill pipe  
1/3 sack hulls, set wooden plug at 35' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 17 1962

CONSERVATION DIVISION  
Wichita, Kansas

6-12-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Box 797 - Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

V. Richard Hoover, Pres. Chief Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover


Box 797 - Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of June, 1962

Carmen Reinhardt Leiker  
Carmen Reinhardt Leiker, Notary Public.

My commission expires Jan. 26, 1963



15-065-00006-00-00

WELL LOG

Chief Drilling Co., Inc.  
P.O. Box 797  
Great Bend, Kansas

SPARKS #1  
NE NE NE Sec. 27-9S-23W  
~~Trego~~ County, Kansas  
~~GRAMM~~

Contractor: Chief Drilling Co., Inc.

Commenced: 5-28-62  
Completed: 6-5-62  
D & A

Casing Record: 8-5/8" @ 200' w/150 sacks Sunset cement

| <u>FORMATION</u> | <u>FROM</u> | <u>TO</u> | <u>ELEVATION</u> |
|------------------|-------------|-----------|------------------|
| Shale & Sand     | 0           | 198       | 2417 Gr.         |
| Shale            | 198         | 1570      | 2419 D.F.        |
| Sand             | 1570        | 1760      | 2422 K.B.        |
| Shale            | 1760        | 1790      |                  |
| Shale & Red Bed  | 1790        | 2008      |                  |
| Anhydrite        | 2008        | 2046      |                  |
| Shale & Shells   | 2046        | 2720      |                  |
| Lime             | 2720        | 2910      |                  |
| Lime & Shale     | 2910        | 3350      |                  |
| Lime             | 3350        | 3960      |                  |
| Total Depth      | 3960        |           |                  |

| <u>FORMATION TOPS</u> |            |
|-----------------------|------------|
| Anhydrite             | 2008 + 414 |
| Heebner               | 3694 -1272 |
| Toronto               | 3715 -1293 |
| Lansing               | 3730 -1308 |
| Base KC               | 3952 -1530 |
| Total Depth           | 3960 -1538 |

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NE NE NE Sec. 27-9S-23W, Trego County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 9th day of June, 1962.

*Carmen Reinhardt Leiker*  
Carmen Reinhardt Leiker,  
Notary Public

My commission expires: Jan. 26, 1963



**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 12 1962

6-12-62

CONSERVATION DIVISION  
Wichita, Kansas