

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Globe Operating, Inc.

Address: P.O. Box 12 Great Bend, Kansas 67530

Phone: (620) 792-7607 Operator License #: 6170

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)
by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-185-23288-00-00

Lease Name: Hullman-Sittner

Well Number: 1

Spot Location (QQQQ): nenuwneSW KCC PKT per CEPS

~~2980~~ 2627 Feet from North / South Section Line

~~1170~~ 3512 Feet from East / West Section Line

Sec. 36 Twp. 21 S. R. 12 East West

County: Stafford

Date Well Completed: _____

Plugging Commenced: 11-11-08

Plugging Completed: 11-13-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	618'	None
				5-1/2"	3680'	2121'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 3220' and 5 sxs. cement. Cut casing loose @2121', pulled up to 650', pumped 15 sxs. gel and 50 sxs. cement @680' pulled up to 300', pumped 40 sxs. cement, pulled up to 40' and circulated 20 sxs. to surface, 60/40 pos, 4% gel.

Plugging Complete

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 315929

Address: P.O. Box 467 Chase, Kansas 67524

RECEIVED
KANSAS CORPORATION
DEC 04 2008
CONSERVATION DIVISION
WICHITA, KS

Name of Party Responsible for Plugging Fees: Globe Operating, Inc.

State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 28th day of November, 2008

[Signature] My Commission Expires: _____
Notary Public

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202