

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Lowry Exploration, Inc.
Address: 427 S. Boston, Suite 306, Tulsa, OK 74103
Phone: (918) 587-5094 Operator License #: 9262
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-4-08 (Date)
by: Lin Reimer (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Atoka Depth to Top: 5468 Bottom: 5472 T.D. _____
Morrow Depth to Top: 5542 1/2 Bottom: 5544 1/2 T.D. 5649
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-175-21323-00-00
Lease Name: Douglas
Well Number: 8-1
Spot Location (QQQQ): _____ - NW - NE - SW
2310 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 36 Twp. 31 S. R. 32 East West
County: SEWARD
Date Well Completed: 10-11-93
Plugging Commenced: 11-4-08
Plugging Completed: 11-5-08


Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	1734	-
ATOKA	OIL & GAS	5468	5472	4 1/2	5750	1788
MORROW	GAS	5542 1/2	5544 1/2			

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Mixed 200 lb. hulls & 20 sx cmt. to plug perms from 5468 to 5544 1/2. Shot & pull 4 1/2 to 1760. Circ. hole w/mud & mixed 50 sx plug from 1760 to 1610. 40 sx 530 to 410. 10 sx 40 to 0. Capped 8 5/8 3 ft. below G.L.

Name of Plugging Contractor: SARGENT & HORTON PLUGGING, INC. License #: 31151
Address: RT. 1, BOX 49BA, TYRONE, OK 73951-9731
Name of Party Responsible for Plugging Fees: LOWRY EXPLORATION, INC.
State of OKLAHOMA County, TULSA, ss.

R.G. LOWRY (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says that he has knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) R.G. Lowry
(Address) 427 S. BOSTON, SUITE 306, TULSA, OK 74103



SUBSCRIBED and SWORN TO before me this 2ND day of DECEMBER, 20 08

My Commission Expires: FEB 20, 2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 04 2008
CONSERVATION DIVISION
WICHITA, KS

[Handwritten signature]