

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company LLC

Address: 125 N Market #1000, Wichita, KS 67202

Phone: (620) 886-5606 x27 Operator License #: 33168

Type of Well: Oil, Gas KCCPKT DEEP 213 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: ~~15-007-21506~~ - 00-00

Lease Name: Smith

Well Number: 4

Spot Location (QQQQ): _____ - S2 - S2 - NE

2310 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 11 Twp. 32 S. R. 12 East West

County: Barber

Date Well Completed: 11-18-82

Plugging Commenced: 11-17-08

Plugging Completed: 11-19-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	390	
				5 1/2	4323	2750

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked up to 5 1/2", pumped 25 sacks, 200# hulls, displace to 3100', max pressure 700, shut in 250, cement at 3100', dug cellar, unpacked casing head, set floor, pulled slips, had 22' stretch, ripped casing at 3010', worked pipe, ripped casing at 2750', pulled casing up to 600', pumped 10 gel, 50 sacks, 100# hulls, pulled to 420', pumped 50 sacks, 100# hulls, pulled to 40' pumped 20 sacks to surface, tore down floor and rig, emptied cellar.


Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67554

Name of Party Responsible for Plugging Fees: Woolsey Operating Company LLC

State of _____ County, _____, ss.

Woolsey Operating Company, LLC (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Col W...

(Address) P.O. Box 168 Medicine Lodge, Ks 67104

SUBSCRIBED and SWORN TO before me this 2nd day of December, 2008

Charlotte C. Hoagland My Commission Expires: 8/23/12
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 04 2008

CONSERVATION DIVISION
WICHITA, KS

2008

My Commission Expires: 8/23/12

[Handwritten initials]