

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Woolsey Operating Company LLC
Address: 125 N Market #1000, Wichita, KS 67202
Phone: (620) 886-5606 x27 Operator License #: 33168
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Steve Durrant (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-007-20,646-00-00
Lease Name: Tedrow
Well Number: 5
Spot Location (QQQQ): N2 - NW - NW
330 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 33 Twp. 32 S. R. 12 East West
County: Barber
Date Well Completed: 7-28-78
Plugging Commenced: 11-13-08
Plugging Completed: 11-17-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	235	
				4 1/2	4563	2610

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Sand at 4450', bailed 4 sacks cement, set floor, pulled slips, had 24" stretch, ripped casing at 3010', worked pipe, ripped casing at 2840', worked pipe, ripped casing at 2610', pipe came free, pulled casing to 600', pumped 10 gel, 50 sacks cement, 100# hulls, pulled to 260', pumped 50 sacks, 100# hulls, pulled to 40', circulated with 20 sacks to surface.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925 RECEIVED
Address: 190 US Highway 56, Ellinwood, KS 67554 KANSAS CORPORATION COMMISSION
Name of Party Responsible for Plugging Fees: Woolsey Operating Company LLC DEC 04 2008
State of _____ County, _____, ss. CONSERVATION DIVISION
WICHITA, KS

Woolsey Operating Company, LLC (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Carl W. Hoagland

(Address) P.O. Box 168 Medicine Lodge, Ks 67104



SUBSCRIBED and SWORN TO before me this 2nd day of December, 20 08
Charlotte C Hoagland My Commission Expires: 8/23/12
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]