

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Woolsey Operating Company LLC  
Address: 125 N Market, #1000, Wichita, Kansas 67202  
Phone: (620) 886-5606 Operator License #: 33168  
Type of Well: Oil, Gas PCKCC per CP23 Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: Steve Durrant (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-007-20963-00-00  
Lease Name: Smith  
Well Number: 1  
Spot Location (QQQQ): \_\_\_\_\_ - NE - NE - SE  
2310 Feet from  North /  South Section Line  
330 Feet from  East /  West Section Line  
Sec. 12 Twp. 32 S. R. 12  East  West  
County: Barber  
Date Well Completed: 8-4-80  
Plugging Commenced: 11-19-08  
Plugging Completed: 11-20-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	214	
				4 1/2	4323	2770

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Hooked up to 4 1/2" casing, pumped 25 sacks, 200# hulls, displaced to 3830', dug cellar, unpacked casing head, cement was at 3830', set floor, pulled slips, cut surface off 4' below ground, had 18" stretch, ripped casing at 3000', worked pipe, ripped casing at 2770', pipe came free, pulled casing up to 600', pumped 10 gel, 50 sacks, 100# hulls, pulled to 240', pumped 50 sacks, 100# hulls, pulled to 40', pumped 20 sacks to surface.


Name of Plugging Contractor: Quality Well Service Inc. License #: 31925

Address: 190 US Highway 56, Ellinwood, KS 67526

Name of Party Responsible for Plugging Fees: Woolsey Operating Company LLC

State of \_\_\_\_\_ County, \_\_\_\_\_, ss.

Woolsey Operating Company, LLC (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Carl W. Furr

(Address) P.O. Box 168, Medicine Lodge, KS 67104

SUBSCRIBED and SWORN TO before me this 2nd day of December 2008

Charlotte C Hoagland My Commission Expires: 8/23/12  
Notary Public

RECEIVED  
KANSAS CORPORATION COMMISSION

DEC 04 2008

CONSERVATION DIVISION  
WICHITA, KS

*PK*