

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oxy USA, Inc
Address: PO Box 2528 Liberal KS 67905
Phone: 620 629 4200 Operator License #: 5447
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)
The plugging proposal was approved on: 9-15-08 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Council Grove Depth to Top: 2757 Bottom: 2844 T.D. 3010'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-093-21371-00-00
Lease Name: Sharp A
Well Number: 3 SW NE
Spot Location (QQQQ): NE SE NW SW
1850 Feet from North / South Section Line
1905 Feet from East / West Section Line
Sec. 10 Twp. 24 S. R. 35 East West
County: Kearny
Date Well Completed: 5-10-94 spud
Plugging Commenced: 10-20-08
Plugging Completed: 10-21-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	951	RECEIVED KANSAS CORPORATION COMMISSION DEC 04 2008 CONSERVATION DIVISION WICHITA, KS
				5 1/2	3010	

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb. hulls + 25 sx cmt. to plug perms from 2757 to 2557, mud spacer to 1850 + mixed 25 sx 1850 to 1650, mud to 800, mixed 100 sx 800 to 0 - plug fell to 240, fill w/H2O to 40, mixed 5 sx 40 to 0 Mixed 8 sx down annulus from 48 to 0 Capped 4 ft. below G.L.

Name of Plugging Contractor: SARGENT AND HORTON PLUGGING, INC. License #: 31151
Address: Rt. 1, Box 49 BA Tyrone, OK 73951-9731
Name of Party Responsible for Plugging Fees: Oxy USA Inc. 1701 N Kansas Av. PO Box 2528 Liberal, KS. 67905
State of Kansas County, Seward, ss.

Kenny Archens (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
(Signature) [Signature]
(Address) PO Box 2528 Liberal, KS. 67905
SUBSCRIBED and SWORN TO before me this 2 day of Dec., 2008
Anita Peterson My Commission Expires: Oct. 1, 2009
Notary Public

ANITA PETERSON
Notary Public - State of Kansas
My Appt. Expires October 1, 2009

Form No: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten initials]