

15-051-01603-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Ellis County, Sec. 10 Twp. 11 Rge. 16 (E) W (W)

Location as "NE/CNW/SW" or footage from lines C S/2 SW SW  
Lease Owner Woodman & Iannitti Drilling Company  
Lease Name Mellor Well No. 1  
Office Address 714 Union National Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 2-12 19 61  
Application for plugging filed 2-12 19 61  
Application for plugging approved 2-12 19 61  
Plugging commenced 2-12 19 61  
Plugging completed 2-12 19 61  
Reason for abandonment of well or producing formation Dry

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3555 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	153	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Bottom Plug 520' with 20 sacks of cement  
Middle Plug 140' with 20 sacks of cement  
Top Plug 40' with 20 sacks of cement

RECEIVED  
STATE CORPORATION COMMISSION  
2-15-1961  
FEB 15 1961

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Woodman & Iannitti Drilling Company  
Address P. O. Box 387, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) K. T. Woodman

714 Union National Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1961

My commission expires December 29, 1964

Agnes L. Kuhn  
Agnes L. Kuhn Notary Public.



D R I L L I N G L O G

Company: Woodman & Iannitti Drilling Company  
 Lease: #1 MEIJOR C S/2 SW SW 10-11-16W  
 Ellis County, Kansas  
 Contractor: Woodman & Iannitti Drilling Company  
 714 Union National Building  
 Wichita, Kansas  
 Date Commenced: 2-2-61  
 Date Completed: 2-12-61  
 Total Depth: 3555'  
 Casing: 8 5/8" at 153' with 120 sacks of cement.

Figures Indicate the Bottom of the Formation

0-330	Shale	2610	Lime
610	Shale Sand	2745	Lime & Shale
700	Sand	2850	Broken Lime
1025	Red Bed	3420	Lime
1125	Shale Shells	3511	Chert
1350	Red Bed	3540	Conglomerate
1770	Shale & Shells	3555	Arbuckle
2370	Lime		
2485	Lime Shale		

GEOLOGICAL TOPS

Elevation	1848 RR
Anhydrite	1030 4818
Heebner	3042 -1194
Toronto	3065 -1217
Iansing	3093 -1245
Cherty Conglomerate	3420 -1572
Simpson Shale	3510 -1662
Arbuckle	3542 -1694
Total Depth	3555 -1707

STATE COMMISSION COMMISSIONER  
 2-15-1961  
 FEB 15 1961  
 COMMISSIONER OF GEOLOGY

I certify the above to be a true and correct copy of the Driller's Log and the geological tops to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

By: K. T. Woodman  
 K. T. Woodman