

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22275-00-01  
Spot: S2SENE Sec/Twnshp/Rge: 32-15S-22W  
2296 feet from N Section Line, 740 feet from E Section Line  
Lease Name: NORTH TRUST Well #: 1-32  
County: TREGO Total Vertical Depth: 4341 feet

Operator License No.: 9855  
Op Name: GRAND MESA OPERATING COMPANY  
Address: 1700 N WATERFRONT PKWY BLDG 600  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1696		200 SX CMT SMDC
PROD	5.5	4340	0	150 SX CMT EA-2
SURF	8.625	218	0	160 SX CMT COMMON 2% GEL, 3% CC
T1	2.875	4318		

141-08

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/25/2008 4:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: JOHN JOHNSON-FIELD SUP Company: GRAND MESA OPERATING COMP Phone: (316) 265-3000

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 200# hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/25/2008 7:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Pumped 50 sxs cement down casing with 200# hulls.  
Pumped 18 sxs gel down casing.  
Pumped 125 sxs down casing with Max. P.S.I. 1050#. S.I.P. 600#.  
Casing went on vacuum.  
Pumped 50 sxs cement down the open top of the casing - not full - let set.  
Tied onto backside - pumped 10 sxs to Max. P.S.I. 500#.  
11/26/2008 - Pumped 35 sxs cement down the casing to fill it up.  
Plug complete.

Perfs:

Top	Bot	Thru	Comments
4278	4285		

**INVOICED**  
DATE 12-23-08  
INV. NO. 2009060904

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 03 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: SWIFT CEMENTING COMPANY-TICKET #15146.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

DEC 01 2008

PKT


Replacement Card

GRAND MESA OPERATING CO  
WICHITA KS 67202

32-15S-22W  
2296'FNL & 740'FEL, SEC  
KANSAS

#1-32 NORTH TRUST OWWO

Cty: TREGO Spot: NE SW SE NE API 15-195-22275  
Site: 4-1/2 N & 2-3/4 W OF BROWNELL KS Lat/Long: 38.70470 -99.78599  
Field: PAGE CREEK SW (EXT 1/4)  
FR: 05/16/2005 Spd: 04/25/2005 Drig Cp: 04/25/2005 Issued: 05/16/2005 Revised: 09/10/2007



Copyright 2007 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

**IP Status:**  
OIL, P 10 BO & 2 BWPD, CHER 4278-4285, 5/1/2005  
**Revisions:** CORR & INFO REL: 9/10/2007 - CORR OLD  
PFS; ADDED TOPS, DSTS & IP  
**Notes:** INFO REL 5/16/2005 - WAS OIL WELL - TIGHT HOLE  
**Contr:** UNKNOWN  
**Geol:** NONE  
**Elev:** 2329 KB  
**Formation Tops:** (L-Log, S-Sample, D-Driller)

L SC	1670 +659
L HEEB	3688 -1359
L LANS	3723 -1394
L BKC	4010 -1681
L PAW	4088 -1759
L FT SC	4178 -1849
L CHER SH	4194 -1865
L CONG	4255 -1926
L CHER SD	4270 -1941

L OSAGE	4298 -1969
PBTD	4324 -1995
RTD OLD	4340 -2011
LTD OLD	4341 -2012

**Old Info:**

**Well Record:** GRAND MESA OPERATING CO,  
#1-32 NORTH TRUST, SPD 01/11/2005, DC  
01/19/2005, 8-5/8" 218 / 160 SX (ALT 2), 5-1/2"  
4340 / 150 SX, DV TOOL AT 1696 / 200 SX, OIL, P  
48 BOPD, NW, CHER 4270-4278, 2/12/2005(CARD  
ISSUED 04/04/2005)  
**Contr:** MALLARD JV #1  
**Geol:** WESLEY D. HANSEN  
**Find:**  
COMMENT: MI & RURT 1/10/2005  
NO CORES