

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20177-00-00
Spot: NENWNW Sec/Twnshp/Rge: 18-5S-21W
4950 feet from S Section Line, 4290 feet from E Section Line
Lease Name: NOONE Well #: 5
County: NORTON Total Vertical Depth: 3520 feet

Operator License No.: 9559
Op Name: PATTERSON, JERRY DBA JERRY PATT
Address: PO BOX 307
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3514	0	w/160 sxs cmt
SURF	8.625	205	0	w/165 sxs cmt

114.40

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/24/2008 10:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JERRY PATTERSON Company: JERRY PATTERSON OIL Phone: (785) 689-4897

Proposed Plugging Method: Ordered 180 sxs 60/40 pozmix - 4% gel - 225# hulls - 10 sxs gel spacer.
Perforated at 1700' - 1000' - 200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/24/2008 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3150' - pumped 10 sxs gel spacer with 40 sxs 60/40 pozmix - 4% gel and 200# hulls.
Pulled tubing to 1700' - pumped 30 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1000' - pumped 40 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 200' - pumped 20 sxs 60/40 pozmix - 4% gel to circulate to surface - closed backside and pumped 40 sxs 60/40 pozmix to circulate 8 5/8" to surface.
Pulled all tubing and topped off 4 1/2" with 5 sxs 60/40 pozmix - 4% gel.

Perfs:

Top	Bot	Thru	Comments
3515	3533		LKC
3511	3514		REGAN
3240	3252		TORONTO

INVOICED
DATE 12-23-08
INV. NO. 2009060905

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 02 2008

Remarks: SWIFT CEMENTING SERVICES-TICKET #15311.

CONSERVATION DIVISION
WICHITA, KS

Plugged through: TBG

District: 04

Signed

Pat Bedore

(TECHNICIAN)

CM

Form CP-2/3

DEC 01 2008

PKT

OZARK ENTERPRISES

P.O. BOX 427

#5 NOONE

18-5-21W
NE NW NW

LOGAN, KS 67646

CONTR ABERCROMBIE DRILLING CTY NORTON

GEOL ROGER WELTY FIELD DENSMORE

E 2091 KB CM 5/30/80 CARD ISSUED 8/14/80 IP P 12 BO & 30 BWPD
2086 GL REAG OH 3512-16
API 15-137-20,177

+	+
+	+
+	+
+	+

SMP	TOPS	DEPTH	DATUM
ANH		1686	+ 405
B ANH		1715	+ 376
HEEB		3223	-1132
TOR		3249	-1158
LANS		3263	-1172
B KC		3452	-1361
REAG		3513	-1422
RTD		3516	-1425

8-5/8" 205/165sx, 4 1/2" 3512/160sx
NO DST'S
MICT -- CO, (REAG OH) 3512-16, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS