

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-173-19072-00-00  
Spot: E2E2E2NE Sec/Twnshp/Rge: 9-27S-1E  
1320 feet from N Section Line, 114 feet from E Section Line  
Lease Name: RECTIFIER Well #: 598  
County: SEDGWICK Total Vertical Depth: 305 feet

Operator License No.: 6035  
Op Name: ONEOK, INC. DBA KANSAS GAS SERVI  
Address: 7421 W 129TH ST  
OVERLAND PARK, KS 66213

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10	127		

35.00

Well Type: CB UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2008 8:00 AM

Plug Co. License No.: \_\_\_\_\_ Plug Co. Name: \_\_\_\_\_

Proposal Rcvd. from: DALE HAYSE, HAYSE MAN Company: \_\_\_\_\_ Phone: (620) 548-2369

Proposed Plugging Method: REMOVE COKE BACKFILL AND ANODE WIRES FROM BORE HOLE. PUMP GROUT THROUGH TREMIE PIPE AND FROM TD (300') TO 3 FEET BELOW SURFACE. BACKFILL AND GRADE SOIL TO ORIGINAL CONDITION.

Plugging Proposal Received By: DAVE WERTZ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/13/2008 5:35 PM KCC Agent: DAVE WERTZ

Actual Plugging Report:

ALL CORE WAS WASHED FROM WELL BORE, ALSO ALL ANODE WIRES WERE PULLED OUT. DRILL PIPE WAS RUN TO 300', CMT WAS CIRCULATED TO SURFACE WITH 5 YARDS OF SLURRY MIX.

Perfs: \_\_\_\_\_

INVOICED  
DATE 12-23-08  
INV. NO 2009060906

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 03 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: LAFARGE SLURRY MIX 5 YDS

Plugged through: DP

District: 02

Signed David Wertz  
(TECHNICIAN)

PK