

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21091-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 31-20S-5W
990 feet from N Section Line, 2310 feet from E Section Line
Lease Name: AJ JOHNSON Well #: 5
County: MCPHERSON Total Vertical Depth: 3412 feet

Operator License No.: 31528
Op Name: KELSO, MIKE OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3407	2149	200 SX
SURF	8.625	205		165 SX

110-89

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/03/2008 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: _____

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: MICHAEL WILSON Witness Type: NONE
Date/Time Plugging Completed: 06/05/2008 11:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SET CIBP @ 3250 & CAP WITH 2SX'S CEMENT, CUT OFF PIPE @ 2149' & PULLED TO 800' & PUMPED 35 SX'S CEMENT WITH 100 LBS., COTTON HULLS, PULL CASING TO 390' & PUMP 100 LBS COTTON HULLS & CIRCULATE 150 SX'S TO SURFACE. PULL CASING OUT & TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3301	3357		

INVOICED
DATE 12-23-08
INV. NO. 2009060907

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 03 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60/40 POZ MIX 4% GEL

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

PK