

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19179-00-00
Spot: NWSESE Sec/Twnshp/Rge: 12-20S-10W
1022 feet from S Section Line, 989 feet from E Section Line
Lease Name: SCHURBERT Well #: 2A
County: RICE Total Vertical Depth: 3302 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
L1	5.5	3256		
PROD	7	3291		<u>107-32</u>
SURF	10.73	142		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2008 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/19/2008 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 2900' AND CAP WITH 5 SX'S CEMENT, PERFORATE @ 1300', 900', AND 250'. RUN TUBING TO 1300' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 900' AND PUMP 50 SX'S CEMENT, PULL TUBING TO 250' AND CIRCULATE CEMENT TO SURFACE. HARD CEMENT WAS PRESENT ON BACKSIDE OF 7". PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2962	2964		

INVOICED
DATE 12-23-08
INV. NO. 2009060909

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 03 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C34257. LOG TECH TICKET #5544. USED 160 SX'S CEMENT.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

PKG