

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-30198-00-01
Spot: NENENE Sec/Twnshp/Rge: 36-20S-13W
5008 feet from S Section Line, 513 feet from E Section Line
Lease Name: C LONNON Well #: 3
County: BARTON Total Vertical Depth: 3571 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3206		
PROD	5.5	3206	0	150 SX
SURF	8.625	217	0	225 SX

Well Type: EOR UIC Docket No: E22531.1 Date/Time to Plug: 10/14/2008 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 400# hulls.
Perf at 300' - 650' - 1400'.
Has 4 1/2" liner ran to the bottom.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2008 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran pipe to 2950' - pumped 200 sxs 60/40 pozmix - 4% gel with 200# hulls - had cement to surface.
Pulled tubing - tied to casing - pumped 200 sxs cement - ran out of cement. Shut down for the day.
10/16/2008 - Went in with tubing - tagged cement at 96' - cut off casing and surface pipe - fill to surface.
12/01/2008 - Casing cut off - topped off with 10 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3258	3329		

INVOICED
DATE 12-23-08
INV. NO. 2009060896

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 04 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT CEMENT SERVICES-TICKET #14743.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

Handwritten initials


DEC 03 2008

11-103

REPL COMP

36-20S-13W

Map No. _____
 OPER CIRCLE OIL COMPANY, INC.
 WICHITA, KANSAS
 WELL #3 LONNON
 CONTR SAGE DRILLING
 FIELD ROLLING GREEN EAST (LANS & ARB)
 I.P. P 40 BOPD-NW (28" X 8" SPM) LANS
 3258-3327 (OA)



S-T-R _____
 SPOT NE NE NE
 CO BARTON, KS.
 ELEV 1871 KB

(KB LOGS:)

HB 3098 -1227
 BL 3221 -1350
 LANS 3237 -1366
 BKC 3464 -1593
 CGR 3474 -1603
 ERO-ARB 3555 -1684
 LTD 3571 -1700
 RTD 3570 -1699

(KB SPLS:)

ANH 658 +1213
 HB 3092
 TOR 3109 -1238
 DG 3128
 BL 3216

DST #1 (LANS) 3235-69, OP 1 HR, 220' GIP, R 30' SLI O
 SPK M, ISIP 120#/30", FP'S 0#-0#, FSIP 80#/30"
 DST #2 (LANS) 3269-3307, OP 1 HR, GTS/11", TSTM, R
 3155' OIL, ISIP 985#/30", FP'S 240#-680#, FSIP
 925#/30"
 DST #3 (LANS) 3296-3350, OP 1 HR, GTS/5", TSTM, R 2520'
 GO (NO GR) ISIP 1000#/30", FP'S 225#-690#, FSIP
 945#/30"
 DST #4 (LANS) 3350-3410, OP 1 HR, R 510' W, ISIP 1130#/
 30", FP'S 0#-0#, FSIP 0#/30"
 RTD 3570, RAN LOG, 5 1/2" @3569' W/150 SX., CO 3350 PBTD,
 12/3324-27 & 16/3306-10 (LANS) NTN, 1500 CRA, 28/3272-
 79 & 12/3258-61 (LANS) NTN, RAN TBG W/PKR @3290, TREAT
 3258-79 W/1000 CRA, PULL TBG & PKR, § LD, § 80 BOPD-NW/

Data Inc