

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-24729-00-00
Spot: SWNW Sec/Twnshp/Rge: 17-19S-14W
3300 feet from S Section Line, 4620 feet from E - Section Line
Lease Name: BIEBERLE Well #: 1
County: BARTON Total Vertical Depth: 3600 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3595	2387	w/135 sxs cmt
SURF	8.625	819	0	w/425 sxs cmt

117.00

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/17/2008 2:30 PM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: ALAN CURTIS Company: GLOBE OPERATING, INC. Phone: (620) 792-7607

Proposed Plugging Method: Ordered 340 sxs 60/40 pozmix - 4% gel - 500# hulls.
Sand off to 3190' - 5 sxs cement on top.
Cut casing off at 2387'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/17/2008 4:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Pulled casing to 1550' - pumped 175 sxs cement with 300# hulls.
Pulled casing to 825' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 250' - pumped 125 sxs cement - circulated.
Pulled casing out - hole stayed full.

Perfs:

INVOICED
DATE 1-6-09
INV. NO. 2009060918

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 23 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #34053.

Plugged through: CSG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

DEC 22 2008

PKG

replacement card

GLOBE OPERATING
GREAT BEND KS 67530-0012

17-19S-14W
C SW NW

#1 BIEBERLE

site 1 N & 4-3/4 W OF GREAT BEND KS	city: BARTON	API 15-009-24729
contr: STERLING DRILLING #1	field: HEIZER WEST	
oper: JAMES C. MUSGROVE		
fr date 12/17/2001	spd date 12/27/2001	drig comp 01/06/2002
	card issued 04/22/2002	last revised 12/09/2002

ELV: 1910 KB, 1902 GL LOG	
tops.....	depth/datum
ANH.....	847 +1063
HER.....	1770 +140
WINF.....	1820 +90
COTTWD.....	2220 -310
NEVA.....	2270 -360
RED E.....	2321 -411
TARK.....	2617 -707
ELMONT.....	2675 -765
TOP.....	2815 -905
HEEB.....	3140 -1230
TOR.....	3158 -1248
DOUG.....	3171 -1261
BR LM.....	3224 -1314

IP status:
OIL, P 7 BO & 5 BWPD, ARB 3542-3545 , 02/01/2002
LANS.....3234 -1324
BKC.....3463 -1553
CONG SD.....3478 -1568
ARB.....3538 -1628
PBTD.....3563 -1653
RTD.....3599 -1689
LTD.....3600 -1690
RTD.....3600 -1690
INFO RELEASED: 12/9/2002 - WAS OIL WELL - TEMP COMP
CSG: 8-5/8" 819 / 425 SX (ALT 1), 5-1/2" 3595 / 135 SX

COPYRIGHT 2002
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)