

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PKT per
OPS
1628

API Well Number: 15-163-22154-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 25-9S-18W
1628 1650 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DEVENY 2423 Well #: 1
County: ROOKS Total Vertical Depth: 3640 feet

Operator License No.: 8925
Op Name: LIBERTY OPER & COMPL, INC
Address: 308 W MILL
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	2.875	3550	0	w/150 sxs cmt
PROD	4.5	3610	0	w/unknown sxs cmt <u>118.30</u>
SURF	8.625	240	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2008 8:00 AM
Plug Co. License No.: 8925 Plug Co. Name: LIBERTY OPER & COMPL, INC
Proposal Rcvd. from: ROGER COMEAU Company: LIBERTY OPER & COMPL, INC Phone: (785) 434-4686

Proposed Plugging Method: Ordered out 160 sxs 60/40 pozmix - 4% gel - 200# hulls.
Squeeze jobs: 500'-740' w/250 sxs; 900'-1100' w/100 sxs.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2008 9:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 75 sxs cement with 100# hulls.
Max. P.S.I. 750#. S.I.P. 750#.
Hooked up to 8 5/8" backside - instant 500#.
Hooked up to 4 1/2"x 2 1/2" annulus - instant 500#.

Perfs:

Top	Bot	Thru	Comments
3516	3520		
3417	3421		

INVOICED
DATE 1-7-09
INV. NO. 2009060923

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 05 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed _____

Richard Williams

(TECHNICIAN)

CM

PKT

REPLACEMENT CARD

S & K ENTERPRISES
 BOX 544
 HOXIE, KS 67740


#1 DEVENY

25-9-18W
 SW NW SE

CONTR CIRCLE M DRILLING CTY ROOKS

GEOLOG MARK TORR FIELD COMEAU EXT (1/8 E)

ELV 2139 KB SPD 9/29/83 CARD ISSUED 2/9/84 IP P 30 BOPD
2134 GL LKC 3417-3520 OA



LOG	Tops	Depth Datum
TOP	3062- 923
HEEB	3277-1138
TOR	3296-1157
LANS	3318-1179
BKC	3546-1407
ARB	3622-1483
RTD	3640-1501

API 15-163-22,154

8 5/8 " 240, 4 1/2 " 3610

DST (1) 3273-3310 (TOR) / 45-45-45-45, REC 30' SGCMW, 480' SGCMW, & SO SPKD M, SIP 691-662#, FP 78-175 / 234-273#, HP 1718-1679#

DST (2) 3359-70 (LKC) / 45-45-45-45, REC 185' SO SPKD MW, SIP 913-903#, FP 68-87 / 107-117#, HP 1767-1660#

DST (3) 3415-25 (LKC) / 45-45-45-45, 115' GIP, REC 65' MO, SIP 546-546#, FP 48-58 / 68-78#, HP 1865-1826#

MICT - CO, PF (LKC K) 3516-20 & (LKC G) 3417-21 (EST), ACIDIZED (AMT NA), SWB DWN, GSO, POP, P 30 BOPD, 11/83

INFO RELEASED: 8/30/84 - ADD PRODUCTION INTERVAL