

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20277-00-00
Spot: N2SWNE Sec/Twnshp/Rge: 10-1S-26W
3300 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HUFF A Well #: 2
County: DECATUR Total Vertical Depth: 3580 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3578	0	w/150 sxs cmt
SURF	8.625	200	0	w/150 sxs cmt <u>116.35</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/21/2008 1:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 443-1031

Proposed Method: Ordered out 250 sxs 60/40 pozmix - 4% gel - 800# hulls.
Fluid level 390' from surface. Anhy 1934' - 1964'.
Squeeze jobs: 900'-1000' w/150 sxs; 1920'-1953'-1500'-1532' w/250 sxs.
New casing leak 971'-1003'. CPBP at 3290'.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2008 5:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2549'. Swift Services pumped 60 sxs 60/40 pozmix - 4% gel with 300# hulls.
Pulled tubing to 1491' - pumped 90 sxs cement with 200# hulls - cwc.
PTOH. Squeezed 4 1/2" casing with 25 sxs cement.
Max. P.S.I. 200#. S.I.P. 200#.
Hooked up to backside - pumped 75 sxs down backside.
Max. P.S.I. 50#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3260	3266		
3254	3258		

INVOICED
DATE 1-7-09
INV. NO. 2009060924

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 05 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3


DEC 02 2008

PET

W. W. SAUVAGE, INC. #2 HUFF "A" 10-1-26W
 404 N. PENN, OBERLIN, KS. N/2 SW NE
 CONTR ABERCROMBIE DRILLING CTY DECATUR

GEOL _____ FIELD LAWSON WEST

E 2471 KB CMO 9/73 CARD ISSUED 1/17/74 IP P EST 50BOPD N/W
LANS 3254-58



API 15-039-20,277

LOG	TOPS	DEPTH	DATUM
ANH		1934	+ 537
B ANH		1964	+ 507
HEEB		3214	- 743
TOR		3248	- 777
LANS		3254	- 783
BKC		3466	- 995
REAG		3555	-1084
GR WASH		3559	-1088
RTD		3580	-1109

8-5/8" 200/150sx; 4 1/2" 3578/150sx
 DST (1) 3221-70/15-45-45-60, 660' GIP,
 420' GO, BHP 360' GMO, 902-850#,
 FP 31-93#, 145-291#
 DST (2) 3268-3308/30-30-30-30, 10'M,
 BHP 385-197#, FP 10-16#
 DST (3) 3416-49/30-30-30-30, 5'M,
 W/SSO, BHP 10-10#, FP 10-10#
 PF 3254-58, A 1500, SWB APPROX 7BOH

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS