

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

*KCC/KP/PS  
APPS*

API Well Number: 15-163-04005-00-01

Spot: W2W2NW

Sec/Twnshp/Rge: 12-9S-17W

*3854 3960* Feet from S Section Line, 4950 feet from E Section Line

Lease Name: BAXA

*5049* Well #: 2

County: ROOKS

Total Vertical Depth: 3466 feet

Operator License No.: 3833

Op Name: SHAIDA, JOHN H.

Address: 4126 N SWEET BAY CIR  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	7	3450	0	w/unknown sxs cmt
PROD	8.625	3192	0	w/150 sxs cmt
SURF	12.5	119	0	w/unknown sxs cmt

*112.65*

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/20/2008 12:00 PM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: JOHN SHADIA

Company: SHAIDA, JOHN H.

Phone: (316) 636-2525

Proposed Plugging Method: Ordered out 600 sxs 60/40 pozmix - 4% gel - 1000# hulls - 28 sxs gel spacer.  
Fluid level at 225'. 7" liner set at 3162' - 3450'.  
CIBP set at 3329'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/20/2008 5:00 PM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Perfs:

Ran tubing to 3110'. Allied pumped 28 sxs gel spacer, followed with 100 sxs 60/40 pozmix - 4% gel with 3% cc and 300# hulls.  
Pulled tubing to 1770' - pumped 75 sxs 60/40 pozmix - 4% gel with 3% cc and 200# hulls.  
Pulled tubing to 1250' - pumped 160 sxs 60/40 pozmix - 4% gel with 500# hulls - heavy mud circulating.  
Pulled to 600' - pumped 100 sxs cement - plugged off annulus.  
Pulled to 500' - pumped 50 sxs - cwc.  
PTOH. Topped off with 5 sxs - casing full.  
Backside full of cement.

**INVOICED**

DATE 1-7-09  
INV. NO. 2009060931

RECEIVED  
KANSAS CORPORATION COMMISSION

**DEC 05 2008**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

*PKT*

**DEC 02 2008**