

6 070769

5-16

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 167-21,776-00-00  
NE, SEC. 30, T 11 S, R 15 W/E  
1260' S feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9125  
Operator: B.A. Younger Oil Co  
Name & Address: Box 451  
Hays, Ks. 67601  
B.A. Younger

1300 W NE Corner feet from E section line  
Lease Name Schmitt Well #1  
County Russell 116.35  
Well Total Depth 3580 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 820

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing Co. License Number \_\_\_\_\_  
Address Box 31, Russell, Ks. 67665

Company to plug at: Hour: PM Day: 16 Month: May Year: 19 89

Plugging proposal received from B.A. Younger  
(company name) B.A. Younger Oil Company (phone) \_\_\_\_\_

were: 8 5/8" 820' S.P. cwc w/500 sks cement. 5 1/2" casing set at 3580' w/150 sks cement.

Perf 3346' - 3360' at bottom sand to 3040' and w/5 sks cement. Recovered 1750' of 5 1/2" casing.

Proposal 200 sks 60/40 Poz 6% Gel and 5 sks Hulls. Pump in with pump truck.

Load 8 5/8" S.P. with cement and shut in under pressure.

Production drilling pulled 5 1/2" casing.

Plugging Proposal Received by Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:00 PM Day: 16 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Poz 8% Gel and 5 sks Hulls pumped in  
with pump truck. 1. Pumped in 8 5/8" S.P. 25 sks cement followed w/175 sks cement w/5 sks  
Hulls mixed in. Max pressure 500 psig. and shut in pressure 250 psig. Cemented by ALLIED  
Cementing. Total cement 200 sks.

RECEIVED  
STATE CORPORATION COMMISSION  
6-6-1989  
JUN 6 1989

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-8-89

INV. NO. 25029

Signed Marion J. Schmidt  
(TECHNICIAN)

Marion J. Schmidt