

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER ~~15-001-02483-00-00~~ 15-001-02483-00-00
NW, NE, SW 1/4 Sec/Twp/Rge S. 2 - T. 24S. - R. 17E.

*KCC PRT
COPS PRT*
2832 feet from south section line
5168 feet from east section line *35.00
29.*

TECHNICIAN'S PLUGGING REPORT

Operator License # 30102

Lease/Well# MENTZER NO. 0W-1

County ALLEN

Operator: ROBERT CHRISTENSEN *cts oil*

Well Total Depth 900' feet

Name & P.O. BOX 41

Production Pipe: 2" Size Feet 900'

Address NEOSHO FALLS, KS. 66758

Surface Casing: 12" Size Feet 40'

AB oil well Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERV. Lic. # 30670-33749

Address: 19245 FORD RD., CHANUTE, KS.

Company to plug at: Hour: 8:00A.M. Day: 27 Month: 8 2008

Plugging proposal received from: MIKE KEPLEY

Company Name: KEPLEY WELL SERV. Phone: 620-431-9212

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part Technician None X

Operations Completed: Hour: 12:00P.M. Day: 27 Month: 8 2008

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 " CASING TO 825'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 " CASING AT SUFRACE. THE 1" PIPE WAS REMOVED. 1" " PIPE WAS WASHED INTO THE 2 " AND 12" ANNULUS TO 425'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 12" SURFACE CASING AT SURFAE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 235 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: SPOT LOCATION ESTABLISHED VIA GPS NAD 83.
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

INVOICED

DATE 1-9-09
INV. NO. 2009060941

RECEIVED Signed:
KANSAS CORPORATION COMMISSION

Clayton P. Titel
TECHNICIAN

DEC 03 2008

CONSERVATION DIVISION
WICHITA, KS

PKT