

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

It is estimated that well was drilled in 1920's.
API NUMBER 15-205-19660-00-00
SW SW SW Sec/Twp/Rge Sec 27, T29S, R15E

228 (GPS) feet from south section line
4936 (GPS) feet from east section line **37.38**

TECHNICIAN'S PLUGGING REPORT

Operator License # 5394

Lease/Well# Volunteer Unit # 14

County Wilson

Operator: R. R. Abderhalden

Well Total Depth 1150 feet

Name & 510 Hardage center
100 S. Main, Suite 510

Production Pipe: NA Size Feet NA

Address Wichita, Kansas 67202

Surface Casing: 12 Size Feet N/A

AB oil well XXXXXX Gas Well

SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: R. R. Abderhalden Lic. # 5394

Address:

Company to plug at: Hour: Day: 8 Month: 10 2008

Plugging proposal received from: Dwain Stout, Field Superintendent

Company Name: R. R. Abderhalden Phone: 316-640-9072

Were: Run cement string to TD and fill with cement from btm to top thru cement string.

INVOICED

DATE 1-8-09

INV. NO. 2009060959

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All Part None XXXXXX

Operations Completed: Hour: Day: 20 Month: 10 2008

Actual Plugging Report: The well was perforated at 1150'. The casing was shot at 509' but the pipe did not come loose. The casing was shot at 349' and the 6.625" and 4.5" casing were removed. A cement string was lowered to 1150' and 20 sacks of cement spotted. The cement string was raised to 509' and 30 sacks of cement spotted. The cement string was raised to 350' and 105 sacks of cement spotted. The cement was tagged at 170' and the well was then filled with an additional 90 sacks of cement. A total of 245 sacks of portland cement were used to plug well.

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: R. R. Abderhalden indicates that the last operator was Sun Oil.
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Alan M. Dunning
TECHNICIAN

PKY