

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*KCC Pkt
Perceps
Sune*

API Well Number: 15-097-21509-00-00

Spot: NENE

Sec/Twnshp/Rge: 8-29S-18W

4848.500 feet from N Section Line,

420 feet from E Section Line

Lease Name: SCHMIDT

520 Well #: 1

County: KIOWA

Total Vertical Depth: 5430 feet

Operator License No.: 32781

Op Name: ROBERTS RESOURCES, INC.

Address: 520 S HOLLAND STE 207
WICHITA, KS 67209

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4760		WITH 2 SX CMT
CIBP		5090		
PROD	5.5	5258	2183	WITH 125 SX CMT
SURF	8.625	602		WITH 300 SX CMT

176.48

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/26/2008 9:25 AM

Plug Co. License No.: 4072

Plug Co. Name: PLAINS, INC

Proposal Rcvd. from: KENT ROBERTS

Company: ROBERTS RESOURCES

Phone: (316) 215-1683

Proposed
Plugging
Method:

CIBP @ 4760' & 2 SX CMT. PLUG AT 1260' WITH 15 SX GEL & 50 SX CMT. PLUG AT 630' WITH 50 SX CMT.
PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/26/2008 11:45 AM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4760' WITH 2 SX CMT. 1ST PLUG AT 1260' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5141	5145		
4951	4957		
4818	4822		

INVOICED

DATE 1-8-09

INV. NO. 2009060960

RECEIVED
KANSAS CORPORATION COMMISSION


DEC 08 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01



Signed Eric MacLaren

(TECHNICIAN)

Form CP-503

Handwritten initials and signature