

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-19168-00-01  
Spot: SEWNWE Sec/Twnshp/Rge: 36-14S-13W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: RUBY Well #: 2  
County: RUSSELL Total Vertical Depth: 3158 feet

Operator License No.: 33636  
Op Name: TRIUNITED INVESTORS, LLC  
Address: 2149 VIZCAYA CIR  
CAMPBELL, CA 95008

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3158	0	w/unknown sxs cmt
SURF	8.625	0	0	w/unknown sxs cmt <u>102.64</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/24/2008 1:30 PM  
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE  
Proposal Rcvd. from: ROGER MOSES Company: TRIUNITED INVESTORS, LLC Phone: (785) 656-1729

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 400# hulls - 7 sxs gel.  
Perfs: 1550' - 650' - 200'.  
11-25-2008 - Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/25/2008 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2800' - pumped 3 sxs gel and 40 sxs cement.  
Pulled tubing to 1550' - pumped 210 sxs cement with 100# hulls - lost circulation.  
Pulled tubing out of the well.  
11/25/2008 - Ran tubing - tagged cement at 765' - pulled tubing to 650' - pumped 40 sxs cement - cement circulated.  
Pulled tubing out - hooked to casing and pumped casing out of ground.  
Hooked to backside and pumped 75 sxs cement - circulated out of casing.  
11/26/2008 - checked fill up - to surface.

**INVOICED**  
DATE 1-8-09  
INV. NO. 2009060961

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 08 2008  
CONSERVATION DIVISION  
WICHITA KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #2950 AND 28940.

Plugged through: TBG

District: 04

Signed R. A. Osked  
(TECHNICIAN) CM

Form CP-2/3

DEC 03 2008

*PEF*

SHELL OIL COMPANY

#2

RUBY

36-14-13W  
SE NW NE

Contr.

RUSSELL

County

E 1680

Comm.

Comp.

9-15-50

IP

66 BOPD & 7 BW

Tops	Depth	Datum
LANS	2815	
ARB	3149	
T.D.	3158	

Casing

4" 3158 OLD WELL WO  
OLD T.D. 3158

PB 2950: PERF 44 S,  
2914-25: ACID 1000:  
32 BO & 19 BW/5 HRS  
PB 2895: PERF 133 S,  
2839-72: ACID 2000:  
PMP 66 BO & 7 BWPD

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

