

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

RECEIVED
@PS

API Well Number: 15-051-21321-00-00

Spot: NESWNW

Sec/Twnshp/Rge: 21-12S-17W

3585 ~~3630~~ Feet from S Section Line, 4290 Feet from E Section Line

Lease Name: DREILING

4418 Well #: 5

County: ELLIS

Total Vertical Depth: 3719 feet

Operator License No.: 33636

Op Name: TRIUNITED INVESTORS, LLC

Address: 2149 VIZCAYA CIR
CAMPBELL, CA 95008

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3600		
PROD	4.5	3714	0	125 SX <u>120.87</u>
SURF	8.625	150	0	400 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/02/2008 4:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: ROGER MOSES

Company: TRIUNITED INVESTORS, LLC

Phone: (785) 656-1729

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls.
Perfs: 1800' - 1125' - 750' - 140'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/02/2008 5:40 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfed at 1800' - 1125' - 750' - 140'.
Hooked up to casing - pumped 230 sxs cement with 500# hulls.
At 300# blew hole in casing.
Cement circulated thru hole.
Hooked up to backside. Max. P.S.I. 500#.

Perfs:

Top	Bot	Thru	Comments
3679	3684		
3566	3569		
3436	3442		

INVOICED

DATE 1-8-09
INV. NO. 2009060961

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 08 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #1081.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Form CP-2/3

DEC 03 2008

PKX

EDWARD P. LEIKER
 MUNJOR ROUTE #5 DREILING 21-12-17w
 HAYS, KS. NE SW NW
 CONTR. RED TIGER DRILG. CO. CTY. ELLIS
 GEOL. FIELD SCHMEIDLER
 E 2131 KB CM 4/11/77 CARD ISSUED 9/15/77 P 28 BOPD N/W
 LKC 3436-3569

	+	+
	+	+

API 15-751-21,321

LOG	TOPS	DEPTH	DATUM
LANS		3400	-1269
BPC		3624	-1493
PENN CONG		3679	-1548
STD		3719	-1588

8-5/8" 150/400sx, 4 1/2" 3714/125sx
 MICT - PF (LKC) 3436-42, SWB 1 BO, PF
 3473-77, SWB 1/2 BO, PF 3566-69, SWB 1/4
 BO, PF (PENN CONG) 3679-84, AC 1000
 REC LD, BP @ 3600, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS