

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PKT 07
OPS

API Well Number: 15-051-22824-00-00

Spot: ~~NW~~ ~~SW~~ ~~NE~~ ~~SE~~

Sec/Twnshp/Rge: 26-13S-20W

1938 ~~2310~~ feet from S Section Line, 998 feet from E Section Line

Lease Name: KRAUS A

1249 Well #: 6

County: ELLIS

Total Vertical Depth: 3900 feet

Operator License No.: 33636

Op Name: TRIUNITED INVESTORS, LLC

Address: 2149 VIZCAYA CIR
CAMPBELL, CA 95008

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3856	0	150 SX
SURF	8.625	250	0	135 SX

126.75

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/21/2008 10:30 AM

Plug Co. License No.: 33930

Plug Co. Name: SUPER OILWELL SERVICE

Proposal Rcvd. from: ROGER MOSES

Company: TRIUNITED INVESTORS, LLC

Phone: (785) 656-1729

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.
Perfs: 2100' - 1520' - 700' - 225'.

Plugging Proposal Received By: CASE MORRIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/21/2008 3:00 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3600' - pumped 13 sxs gel and 50 sxs cement with 200# hulls.
Pulled tubing to 2100' - pumped 260 sxs cement with 300# hulls - cement circulated.
Pulled tubing out - hooked up to casing - pumped 30 sxs cement.
Max. P.S.I. 500#.
Hooked to braden head and pumped one sack cement.
Max. P.S.I. 500#.
12/02/2008 - checked fill up - 70' down.

Perfs:

Top	Bot	Thru	Comments
3806	3812		
3799	3802		

INVOICED

DATE 1-8-09

INV. NO. 2009060961

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 08 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OILWELL CEMENTING-TICKET #1078.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

Form CP-2/3

DEC 03 2008

PKT

