

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-23851-00-00
Spot: S2S2NE Sec/Twnshp/Rge: 2-14S-17W
2938 feet from S Section Line, 1302 feet from E Section Line
Lease Name: BRAUN ALBERT Well #: 2-A
County: ELLIS Total Vertical Depth: 3507 feet

Operator License No.: 33636
Op Name: TRIUNITED INVESTORS, LLC
Address: 2149 VIZCAYA CIR
CAMPBELL, CA 95008

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3507	0	125 SX
SURF	8.625	208	0	140 SX

113.98

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2008 9:30 AM
Plug Co. License No.: 33930 Plug Co. Name: SUPER OILWELL SERVICE
Proposal Rcvd. from: ROGER MOSES Company: TRIUNITED INVESTORS, LLC Phone: (785) 656-1729

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 12 sxs gel.
Perfs: 1800' - 1120' - 500' - 200'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2008 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfed at 1800' - 1120' - 500' - 200'.
Ran tubing to 3300' - pumped 7 sxs gel and 40 sxs cement with 200# hulls.
Pulled tubing to 1800' - pumped 95 sxs cement with 200# hulls - cement circulated.
Pulled tubing out - hooked up to casing - pumped 20 sxs cement.
Max. P.S.I. 500#.
Hooked up braden head and pumped one sack cement.
Max. P.S.I. 500#.

Perfs:

Top	Bot	Thru	Comments
2914	2925		W/ 44 SHOTS
2839	2872		W/ 133 SHOTS

INVOICED
DATE 1-8-09
INV. NO. 2009060961

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 08 2008

Remarks: ALLIED CEMENTING COMPANY-TICKET #35090.

CONSERVATION DIVISION
WICHITA, KS


Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) CM

PKT

EDWARD P. LEIKER
 MUNJOR RT. - BOX 17 #2 "A" BRAUN 2-14-17W
 HAYS, KS 67601 3080' FSL & SW'
 CONTR RED TIGER DRILLING CO. CTY ELLIS 1130' FEL, SEC
 GEOL _____ FIELD IOUION
 ELV 1928 KB SPD 4/19/84 CARD ISSUED 7/19/88 IP P 21 BO & 2.3 BWPD
 ARB 3472-3475



LOG	Tops	Depth/Datum	
*ANH	1104 +	824	API 15-051-23,851 825'8 " 208 / 140SX, 4 1/2 " 3507 / 125SX NS IN LKC ZNS GSO IN TOP 10' OF ARB SFO IN ARB FROM 3472-75 NO DST'S MICT - CO. PF (ARB) 3472-75. W/2 SPF. AC 500G (15% INS), SWB LD, GSO, SET 2 3/8 " TBG AT 3470', POP, P 21 BO & 2.3 BWPD. (GR 32"), 5/28/84
*B/ANH	1141 +	787	
HEEB	3158-	1230	
LKC	3202-	1274	
BKC	3436-	1508	
CONG	3450-	1522	
ARB	3471-	1543	
RTD	3510-	1582	
*DRILLERS TOPS			