

15-065-03259-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 9-20-1957 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Burch Exploration Inc. OPERATORS LICENSE NO. 7448
ADDRESS 11225 Edinborough Way PHONE # 308 345-3214
LEASE (FARM) EATK A Hildebrand WELL NO. 1 WELL LOCATION W 2 SW NE COUNTY GRAHAM
SEC. 28 TWP. 9 RGE. 23 (E) or (W) TOTAL DEPTH 3995' PLUG BACK TO 3814'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. ? _____

SURFACE CASING SIZE 8 3/8" SET AT 554' CEMENTED WITH 350 SACKS

CASING SIZE 5 1/2" SET AT 3994 CEMENTED WITH 1505X SACKS 6 3/4" P 2 MIX SACKS

PERFORATED AT 3930 To 3933, 3840 To 3846, 3832 To 3836, 3795 To 3799 + 3790 To 3793. 1200 LBS Chem Pack (2020)

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Mix 300 LBS. of Hulls w/ 30 SACKS Chem Pack

TOP OF PERFS: Mix 150 SACKS Fill casing to surface. Mix 200 LBS of Hulls w/ 20 SACKS OF 6 3/4" P 2 MIX. Fill 8 3/8" Annulus to surface. Pressure 200 To 400 LBS.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 1-26-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Melvin L. Taylor PHONE # 308 345-3214

ADDRESS 102 E 6th McCook, NE 69001

PLUGGING CONTRACTOR Doc's Well Service LICENSE NO. 6779

ADDRESS P.O. Box 115 Oberlin, KS 67749 PHONE # 913 475-3422

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: J. David Burch
(Operator or Agent)

DATE: 5/9/90

MAY 11 1990
CONSERVATION DIVISION
Wichita, Kansas