

15-065-01557-0600

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER December 3, 1957 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Burch Exploration Inc. OPERATORS LICENSE NO. 7448

ADDRESS 11190 Cambridge Court, Parker, CO 80134 PHONE # (303) 841-9417

LEASE (FARM) Hildebrand WELL NO. 1 WELL LOCATION NW NW NE COUNTY Graham

SEC. 28 TWP. 9 RGE. 23 (E) or (W) TOTAL DEPTH 3948 PLUG BACK TD 3930

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 210 CEMENTED WITH 150 SACKS

CASING SIZE 4 1/2 SET AT 3934 CEMENTED WITH 150 SACKS

PERFORATED AT 3912 to 15, 3896 to 3900, 3877 to 84

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Call state plugger, Carl Goodrow. Mix 400

lbs. of bulls with 30 sks of cement to plug perforations. Fill 4 1/2 to surface w/cement.

Pressure to 500 lbs. pump 40 sks down 8 5/8 casing. Pressure to 500 lbs.
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? _____
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 5-1-87

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Melvin L. Taylor PHONE # (308) 345-3214

ADDRESS 405 East 14th Street, McCook, NE 69001

PLUGGING CONTRACTOR Poe's Well Service LICENSE NO. 6779

ADDRESS P.O. Box 115, Oberlin, KS 67749 PHONE # (913) 475-3422

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Melvin L. Taylor
(Operator or Agent)

DATE: 4-27-87 CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION