



Operator Name: Bramwell Petroleum, Inc. Lease Name: Southwestern College Well #: 3  
 Sec. 36 Twp. 28 S. R. 8  East  West County: Kingman

**INSTRUCTIONS:** Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken  Yes  No  
 (Attach Additional Sheets)  
 Samples Sent to Geological Survey  Yes  No  
 Cores Taken  Yes  No  
 Electric Log Run  Yes  No  
 (Submit Copy)

Log Formation (Top), Depth and Datum  Sample  
 Name Mississippi Top Datum  
 4079-2463

List All E. Logs Run:

Dual Induction; Dual compensated porosity;  
 cement bond log

CASING RECORD <input type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs./ Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4	8 5/8	23	206	60-40 poz	175	2% gel 3% Cacl
Production	7 7/8	4 1/2	10 1/2	4151	USC	125	None

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
2	4082-4088	None	

TUBING RECORD		Size	Set At	Packer At	Liner Run
		2 3/8	4118	N/A	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr. Sigw		Producing Method <input checked="" type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity
		260	3	N/A	

Disposition of Gas  Vented  Sold  Used on Lease (If vented, Submit ACO-18.)  
 METHOD OF COMPLETION  Open Hole  Perf.  Dually Comp.  Commingled  
 Other (Specify) \_\_\_\_\_

**RECEIVED**  
**MAR 28 2006**  
**KCC WICHITA**



# United Cementing and Acid Co., Inc.

7167

SERVICE TICKET  
6804

Oil Well Cementing & Acidizing  
(316) 321-4680 • 800-794-0187 • FAX (316) 321-4720  
2510 West 6th Street • El Dorado, KS 67042

DATE 2-12-05

COUNTY Kingman CITY \_\_\_\_\_

CHARGE TO Brownwell oil

ADDRESS \_\_\_\_\_ CITY \_\_\_\_\_ ST \_\_\_\_\_ ZIP \_\_\_\_\_

LEASE & WELL NO. Southwest College # 3 CONTRACTOR \_\_\_\_\_

KIND OF JOB Long String SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_

DIR TO LOC \_\_\_\_\_ OLD NEW

Quantity	MATERIAL USED	Serv. Charge
125.52	U.S.C. Cement @ 9.5%	
500 gal	mad Flush @ 1.00	
4	4 1/2 Centralizer @ 29.74	
1	4 1/2 A-F4 6-wide shoe	194.99
	BULK CHARGE	
	BULK TRK. MILES	
84	PUMP TRK. MILES	
1	PLUGS 4 1/2 Rubber Plug @ 38.09	
	SALES TAX 10.30	
	TOTAL	1007.60

T.D. \_\_\_\_\_ CSG. SET AT 4145 VOLUME 67

SIZE HOLE \_\_\_\_\_ TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

MAX. PRESS. 400 FF SIZE PIPE 4 1/2

PLUG DEPTH 4145 PKER DEPTH \_\_\_\_\_

PLUG USED \_\_\_\_\_ TIME ON LOCATION 9:15 TIME FINISHED 11:30

REMARKS: Pump 10 Barrel water - 12 Barrel mad Flush mix 125.52 U.S.C. Release Plug Displace Plug to 4145. Plug held. Remove Plug Centerline.

RECEIVED  
MAR 28 2006

EQUIPMENT USED		KCC WICHITA
NAME	UNIT NO.	
<u>Chief # B-14</u>		OWNER'S REP.
<u>Ron Pitts</u>		
CEMENTER OR TREATER	NAME	
	<u>John S. # B-1</u>	



# United Cementing and Acid Co., Inc.

Oil Well Cementing & Acidizing  
 (316) 321-4880 • 800-794-0187 • FAX (316) 321-4720  
 2510 West 5th Street • El Dorado, KS 67042

7151

## SERVICE TICKET

6661

DATE 12-2-05

COUNTY Kingsman CITY \_\_\_\_\_

CHARGE TO Bramwell Petroleum Inc.

ADDRESS 15183 SW 25th Ave

CITY Wiley ST KS ZIP 67142

LEASE & WELL NO. Southwest College #3

CONTRACTOR Ace Drill-It

KIND OF JOB Surface

SEC. 36 TWP. 28 RNG. 8 W

D/R TO LOC Kingsman Hwy 14 South to SW 25th Street North 1/2

OLD  NEW

Quantity	MATERIAL USED	Serv. Charge	
			500.00
175 sks	60/40 po2 2% gel + 3% cc		875.00
45 sks	gel		40.00
5 sks	Calcium Chloride		131.00
1	8 5/8" centerizer		50.00
184 sks	BULK CHARGE		180.32
82	BULK TRK. MILES <u>9.210 mi</u>		603.52
82	PUMP TRK. MILES		184.50
1	PLUGS <u>8 5/8" WRC</u>		
		105.50	SALES TAX
			TOTAL
			2996.90

TD. 210 ft.

CSG SET AT 210 ft. VOLUME \_\_\_\_\_

SIZE HOLE 12 1/4"

TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

MAX. PRESS \_\_\_\_\_

SIZE PIPE 8 5/8" 24" New

PLUG DEPTH 192 ft.

PKER DEPTH \_\_\_\_\_

PLUG USED 1 - 8 5/8" WRC

TIME ON LOCATION 12:00 TIME FINISHED \_\_\_\_\_

REMARKS: Ran 8 5/8" to 210 ft. Brake circulation, Mix pump 175 sks 60/40 po2 2% gel 3% cc. Shutdown, Release 8 5/8" WRC Plug to disp cement to 192 ft. & Shut in. Cement did circulate in the cellar.

RECEIVED

MAR 28 2006

EQUIPMENT USED  
 NAME UNIT NO. NAME UNIT NO.  
Shawn Scobee P-14  
Jim Thomas 24  
 CEMENTER OR TREATER

OWNER'S REP.  
Dan Hamme B-1  
 KCC WICHITA