

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21443-00-01
Spot: NWNWNWNE Sec/Twnshp/Rge: 21-7S-19W
5017 feet from S Section Line, 2326 feet from E Section Line
Lease Name: KOPPES Well #: 1-21 SWD
County: ROOKS Total Vertical Depth: 3436 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3455		150 SX
SURF	8.625	332		225 SX

111.67

Well Type: SWD UIC Docket No: D20752.0 Date/Time to Plug: 01/07/2009 9:30 AM
Plug Co. License No.: 8061 Plug Co. Name: OIL PRODUCERS INC. OF KANSAS
Proposal Rcvd. from: BRANDON SIROKY Company: Phone: (316) 215-1357

Proposed DV - 1288' w/ 225 sx cmt.
Plugging PBTB - 1250'
Method: Bad casing @ 989'. Unable to get deeper than 1070'.
Perfs @ 1060 - 1128'
Order 300 sx 60/40 pozmix 4% gel and 600 lbs hulls

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 01/07/2009 11:15 AM KCC Agent: DAVID WANN

Actual Plugging Report:

Run tubing and spot 75 sx cmt @ 1055'
Pull tubing, tie on to casing and pump 200 sax cmt w/ 600 lbs hulls.
Shutin 600 psi.
Tie onto braden head - instant pressure.

Perfs:

Top	Bot	Thru	Comments
1060	1120		CEDAR HILLS

INVOICED
DATE 1-27-09
INV. NO. 2009061119

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 12 2009


CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through:

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3



JAN 08 2009

PETRO-MINING RESOURCES, INC. REPLACEMENT CARD

P.O. DRAWER 298
 OBERLIN, KS 67749

#1-21 KOPPES


21-7-19W
 100' NW,

CONTR CIRCLE M DRILLING COMPANY CTY ROOKS

C NW NW NE

GEOL BLOND FARMER

FIELD GROVER WEST



ELV 1965 KB SPD 11/10/81 CARD ISSUED 6/17/82 IP SWDW

AP I 15-163-21,443

GED HILLS 1060-1120

LOG	Tops	Depth Datum
ANH	1470 +	495
B/ ANH	1492 +	473
TOP	2908 -	943
HEEB	3112 -	1147
TOR	3134 -	1169
LANS	3155 -	1190
BKC	3374 -	1409
ARB LM	3401 -	1436
SDY ARB	3412 -	1447
LTD	3431 -	1466
RTD	3456 -	1491

8 5/8 " 332/225SX; 5 1/2 " 3455
 DST (1) 3415-32 (ARB) / 30-60-30-60, BLEW 3/4 " IN BUCKET
 BOTH OP'S, REC 30' FO, 30' HO & GSY M (30% OIL, 3% G, 67%
 M), SIP 957-851#, FP 38-38 / 48-48#, HP 1925-1858#
 DST (2) 3436-56 (ARB) / 30-60-30-90, REC 5' FO, 25' HO &
 GCM (40% OIL, 12% G, 48% M), REC 50' OCM (25% OIL), SIP
 880-832#, FP 48-58 / 67-77#, HP 1925-1848#
 MICT - CO, PF (ARB) 3418-22, ACIDIZED (AMT NA), SWB DWN,
 SO, PF (LKC J) 3330-34 W/4 SPF, ACIDIZED (AMT NA), SWB
 DWN, SO, POP, P 2 BO & 200 BWPD, FROM BOTH ZNS, NON-
 COMMERCIAL, CONVERTED TO SWDW, PF (CED HILLS) 1060-
 1120 W/2 SPF, SWDW - INJECTION RATE SATISFACTORY

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

INFO RELEASED: 6/9/83 - WAS OIL WELL - TIGHT HOLE