

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-00113-00-01
Spot: NENENW Sec/Twnshp/Rge: 4-22S-9W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: J H FAIR Well #: 1
County: RENO Total Vertical Depth: 3641 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3641	1405	
SURF	8.625	236		
T1	2.375	3125		

118.33

Well Type: SWD UIC Docket No: E27539.1 Date/Time to Plug: 11/02/2008 5:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ROBIN AUSTINE Company: RAMA OPERATING CO., INC. Phone: (620) 234-5191

Proposed
Plugging
Method:

ACCORDING TO THE RULES AND REGULATIONS OF THE KCC

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL
Date/Time Plugging Completed: 11/03/2008 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3100' PLACED 5 SX OF CEMENT ON TOP OF SASND, LOG TECH SHOT OFF CASING @ 1405' PULLED CASING TO 1360' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 1000' SPOTTED 35 SX OF CEMENT, PULLED CASING TO 537' SPOTTED 140 SX OF CEMENT AND 50 LBS OF HULLS, PULLED CASING TO 279' CIRCULATED 100 SX OF CEMENT AND 50 LBS OF HULLS TO SURFACE. CHECKED TOP PLUG 11/4/2008 WITH IN 5' OF SURFACE OK TO CLOSE.

Perfs:

Top	Bot	Thru	Comments
3478	3488		
3170	3174		

INVOICED

DATE 1-27-09
INV. NO. 2009061122

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2009

Remarks: COPELAND CEMENT OUT OF GREAT BEND, KS. TICKET #34250 60-40 POS, MIX

Plugged through: CSG

District: 02

Signed

B. J. Hope

(TECHNICIAN)

PS