

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

*FOR KCC PERM
KCC PERM*

API Well Number: 15-095-21738-00-00
Spot: S2S2S2W *re-seal SWSW*
Sec/Twnshp/Rge: 7-27S-9W
330 feet from S Section Line, 3960 feet from E Section Line
Lease Name: BRADSHAW Well #: 1
County: KINGMAN Total Vertical Depth: 1752 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: PO BOX 48788
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1748	1330	100 SX
SURF	8.625	273		200 SX

56.94

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/12/2008 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING AND SALVAGE Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK PERFS TO 1520 AND CAP WITH 4 SKS OF CMT. 35 SKS 975', CIRC CMT 323-0'

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 12/12/2008 2:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:
THE PERFS WERE COVERED WITH SAND TO 1520', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1330', AND PULLED TO 976', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRC TO SURFACE. THE REMAINING CASING WAS PULLED AND THE CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
1596	1614		
1576	1580		

INVOICED
DATE 1-27-09
INV. NO. 2009061124

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: COPELAND CMTG 60/40 4% GEL
Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

[Handwritten initials]