

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-30116-00-00  
Spot: SENE Sec/Twnshp/Rge: 15-30S-19W  
3300 feet from S Section Line, 660 feet from E Section Line  
Lease Name: NEUMANN A Well #: 1  
County: KIOWA Total Vertical Depth: 5150 feet

Operator License No.: 32781  
Op Name: ROBERTS RESOURCES, INC.  
Address: 520 S HOLLAND STE 207  
WICHITA, KS 67209

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 2 SX CMT
PROD	4.5	5149	2643	WITH 175 SX CMT <b>167.38</b>
SURF	8.625	518		WITH 450 SX CMT

Well Type: OIL **33645** UIC Docket No: H2Plains LLC Date/Time to Plug: 01/05/2009 9:40 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC **KCC PRT per Licensing Phone: (785) 798-3995**  
Proposal Rcvd. from: EDGAR SANCHEZ Company: PLAINS, INC

Proposed Plugging Method: SET CIBP @ 5000' WITH 2 SX CMT. PLUG AT 1260' WITH 12 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/05/2009 12:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1260' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5086	5089		
5060	5066		


**INVOICED**  
DATE 1-28-09  
INV. NO. 2009061125

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 09 2009  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01



Signed Eric MacLaren  
(TECHNICIAN)